

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	3277R	COOK	66	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62296				

STATE STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-02	TEMPORARY EROSION CONTROL SYSTEMS
420001-06	PAVEMENT JOINTS
606001-02	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-02	PC CONCRETE ISLANDS AND MEDIANS
664001-01	CHAIN LINK FENCE
701301-02	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701501-03	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-03	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-06	TRAFFIC CONTROL DEVICES
704001-02	TEMPORARY CONCRETE BARRIER
813001-01	JUNCTION BOXES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED)
- ALL UTILITIES, SCHOOL DISTRICTS, LOCAL POLICE, AND FIRE DEPARTMENTS SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.
- NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET. US ROUTE 6 (159TH STREET) SHALL BE KEPT OPEN TO TRAFFIC DURING THIS PROJECT.
- 10-FOOT TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE ITEM OF WORK SPECIFIED.
- WHERE ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- FOR STABILIZATION, CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SAND BAGS ON EACH TYPE I OR II BARRICADES AND FOUR (4) ON EACH TYPE III BARRICADES.
- ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM.
- SPECIAL ATTENTION IS CALLED TO ARTICLE 107.12 REGARDING RAILROAD FLAGGERS. THE NAME AND TELEPHONE NUMBER OF THE RAILROAD ENGINEER IS
CANADIAN NATIONAL MR. THOMAS TUCKER (248) 740-6227
- COOPERATION WITH UTILITIES: THE APPLICABLE PORTIONS OF ARTICLES 105.07 AND 107.31 OF THE STANDARD SPECIFICATIONS SHALL APPLY. THE FOLLOWING UTILITY CONTACT INFORMATION IS THE BEST INFORMATION AVAILABLE TO THE DEPARTMENT AND IS INCLUDED FOR THE CONVENIENCE OF THE BIDDER:

COMMONWEALTH EDISON CO.
DONALD RICHARD RIES
PROJECT ENGINEER
7601 S. LAWDALE AVE.
CHICAGO, IL 60652
TEL (773) 838-2905
PAGER (888) 610-9349
FAX (773) 838-4117
EMAIL: DONALD.RIES@EXELONCORP.COM

MCLEOD USA
PAUL BAUMANN
900 COMMERCE DRIVE, SUITE 203
OAKBROOK, IL 60523
TEL (630) 570-5174
CELL (312) 296-4825
PAGER (877) 541-0267
FAX (630) 570-5005
EMAIL: PBAUMANN@MCLEODUSA.COM

CURTIS CHAMPAGNE
PROJECT PLANNER
MILFORD ENGINEERING COMPANY
P.O. BOX 60170
SAN ANGELO, TX 76906
TEL (325) 223-9111
CELL (573) 489-5015
FAX (325) 944-4063
EMAIL: CURTIS@MILFORD-ENG.COM

SPECIAL WASTE

THE PROJECT SITE IS KNOWN TO CONTAIN CONTAMINATED SOIL. ATTENTION IS DRAWN TO SECTION 669 OF THE STANDARD SPECIFICATION AND TO THE SUPPLEMENTAL SPECIFICATION FOR REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.

THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK (LUST) CLEANUPS OR THAT IS PREQUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

THE CONTRACTOR, ANY SUBCONTRACTORS, AND ANY UTILITY EXCAVATING MATERIAL WITHIN THESE AREAS MUST BE NOTIFIED OF THE POTENTIAL SOIL CONTAMINATION. THE FOLLOWING SITES CONTAIN CONTAMINATED SOIL AND SHOULD BE MONITORED BY THE ENVIRONMENTAL FIRM FOR SOIL CONTAMINATION AND WORKERS PROTECTION:

- STATION 92+50 TO STATION 94+00,
0 TO 70-FEET LT (CANADIAN NATIONAL RAILROAD,
SITE 814-23/814A-2/814B-1, 15840 SOUTH WEST AVENUE) -
NON-SPECIAL WASTE.
CONTAMINATES OF CONCERN SAMPLING PARAMETERS: PNA' s.

ANY WASTE GENERATED AS A SPECIAL WASTE OR A WASTE NOT CERTIFIED AS A NON-SPECIAL WASTE FROM THIS PROJECT SHOULD BE MANIFESTED OFF-SITE USING THE GENERATOR NUMBER FOR COOK COUNTY (0318995023).

INDEX OF SHEETS

SHEET NO.	DRAWING TITLE
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES AND STATE STANDARDS
3-4	SUMMARY OF QUANTITIES
5	EXISTING & PROPOSED TYPICAL SECTIONS
6-7	ALIGNMENT, TIES AND BENCHMARKS
8-10	MAINTENANCE OF TRAFFIC
11	PLAN AND DRAINAGE DRAWING
12	ROADWAY CONSTRUCTION DETAILS
13	RAILROAD UTILITY RELOCATION PLAN
13A-13C	PLAT OF HIGHWAYS
14-18	LIGHTING PLANS AND DETAILS
19-48	STRUCTURE PLANS - STRUCTURE NO. 016-2754
49-50	RETAINING WALL DETAILS
51	TRACK CONSTRUCTION - QTY'S, NOTES & TYPICAL SECTIONS
52-53	TRACK CONSTRUCTION - GENERAL PLAN
54	TRACK CONSTRUCTION - TRACK PROFILES
55-56	TRACK CONSTRUCTION - TRACK CONSTRUCTION STAGING PLAN
57-66	TRACK CONSTRUCTION - CROSS SECTIONS

COMMITMENTS

CONSTRUCTION ACTIVITIES ARE TO INCLUDE COORDINATION WITH INGALL'S HOSPITAL FOR ROUTING OF EMERGENCY VEHICLES DURING CONSTRUCTION.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM I-294 TO IL RTE 1
INDEX OF SHEETS, GENERAL NOTES
AND STATE STANDARDS

DATE 03/27/06
DRAWN BY VAP
CHECKED BY JRP