

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	3277R	COOK	66	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

80% FED. / 20% STATE CONTRACT NO. 62206

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% FED. / 20% STATE CONSTRUCTION TYPE CODE			
				RETAINING WALL & MINOR ROADWAY	RAILROAD BRIDGE OVER ROADWAY	RAILROAD TRACK & RAIL	ROADWAY LIGHTING **
				Y007	X631-5B	J000-5B	Y030-1E
				<i>URBAN</i>			
20200100	EARTH EXCAVATION	CU YD	5842			5842	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1113	299	814		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3870			3870	
25000210	SEEDING, CLASS 2A	ACRE	0.8			0.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72			72	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72			72	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72			72	
25100630	EROSION CONTROL BLANKET	SQ YD	7740			7740	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	100			100	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80			80	
28000300	TEMPORARY DITCH CHECKS	EACH	13			13	
28000400	PERIMETER EROSION BARRIER	FOOT	732	310		422	
28000500	INLET AND PIPE PROTECTION	EACH	1			1	
28000510	INLET FILTERS	EACH	2	2			
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	93	93			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2538	2538			
44000100	PAVEMENT REMOVAL	SQ YD	125	125			
44000300	CURB REMOVAL	FOOT	125	125			
44000600	SIDEWALK REMOVAL	SQ FT	2538	2538			
44003100	MEDIAN REMOVAL	SQ FT	125	125			
50102400	CONCRETE REMOVAL	CU YD	182.0		182.0		
50200100	STRUCTURE EXCAVATION	CU YD	1018	528	490		
50300225	CONCRETE STRUCTURES	CU YD	960.6	139.7	820.9		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	170.1		170.1		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50800105	REINFORCEMENT BARS	POUND	18850		18850		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	193470	8800	184670		
51000305	PIPE HANDRAIL, SPECIAL	FOOT	208		208		
51500100	NAME PLATES	EACH	1		1		
54205059	PIPE CULVERTS, SPECIAL 24"	FOOT	62		62		
54213879	STEEL END SECTIONS 24"	EACH	2		2		
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	160	160			
58000110	MEMBRANE WATERPROOFING (SPECIAL)	SQ FT	5773		5773		
58700200	BRIDGE SEAT SEALER	SQ FT	634		634		

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% FED. / 20% STATE CONSTRUCTION TYPE CODE			
				RETAINING WALL & MINOR ROADWAY	RAILROAD BRIDGE OVER ROADWAY	RAILROAD TRACK & RAIL	ROADWAY LIGHTING **
				Y007	X631-5B	J000-5B	Y030-1E
				<i>URBAN</i>			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	361	139	222		
60100915	PIPE DRAINS 6"	FOOT	108	108			
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	311	141	170		
60600605	CONCRETE CURB, TYPE B	FOOT	131	131			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	150	150			
66400570	CHAIN LINK FENCE, 8' (SPECIAL)	FOOT	1248			1248	
66410300	CHAIN LINK FENCE REMOVAL	FOOT	1262			1262	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	357	178	179		
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	380	380			
• 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2			
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	112	112			
• 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	25	25			

• DENOTES SPECIALTY ITEM  
 \*\* 100% CITY OF HARVEY  
 NP - NON-PARTICIPATING

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 FROM I-294 TO IL RTE 1 SUMMARY OF QUANTITIES
NAME	DATE	

DRAWN BY VAP  
CHECKED BY JRP

DATE 03/27/06