F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	* 2003-0291	COOK	344	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62581

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKING- LINE 4" (FOOT)
MOT-02		2638+00	75+94	
I-94/90	WHITE			1,440
	YELLOW			1,650
MOT-03		75+94	87+94	
I-94/90	WHITE			2,273
	YELLOW			2,733
	6'S-2'D			78
MOT-04		87+94	99+94	
I-94/90	WHITE			3,190
	YELLOW			2,224
MOT-05		99+94	111+94	
I-94/90	WHITE			3,144
	YELLOW			2,400
MOT-06		111+94	125+39	
I-94/90	WHITE			3,719
	YELLOW			2,365
MOT-08		125+39	137+39	
I-94/90	WHITE			2,717
	YELLOW			3,063
	6'S-2'D			81
MOT-09		137+39	149+39	
I-94/90	WHITE			5,205
	YELLOW			3,625
MOT-10		149+39	161+39	
I-94/90	WHITE			2,546
	YELLOW			2,619
MOT-11		161+39	173+25	
I-94/90	WHITE			2,400
	YELLOW			2,400
MOT-12		173+25	184+51	
I-94/90	WHITE			2,400
	6'S-2'D			36
	YELLOW			2,452
MOT-13		184+51	196+51	
I-94/90	WHITE			1,896
	6'S-2'D			47
	YELLOW			2,174
MOT-14		196+51	208+51	
I-94/90	WHITE			254
	YELLOW			254
MOT-15	WHITE	208+51		2,420
			TOTAL	61,805

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKING- LINE 5" (FOOT)
MOT-02		2638+00	75+94	
I-94/90	10D-30S			750
MOT-03		75+94	87+94	
I-94/90	10D-30S			346
MOT-04		87+94	99+94	
I-94/90	10D-30S			715
MOT-05		99+94	111+94	
I-94/90	10D-30S			616
MOT-06		111+94	125+39	
I-94/90	10D-30S			600
MOT-08		125+39	137+39	
I-94/90	10D-30S			600
MOT-09		137+39	149+39	
I-94/90	10D-30S			560
MOT-10		149+39	161+39	
I-94/90	10D-30S			186
MOT-12		173+25	184+51	
I-94/90	10D-30S			110
MOT-13		184+51	196+51	
I-94/90	10D-30S			314
MOT-14		196+51	208+51	
I-94/90	10D-30S			117
			TOTAL	4,913

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKINGS - LTR & SYM (SQ FT)
MOT-14		196+51	208+51	
I-94/90	ARROW			15.6
	AND ONLY			20.8
MOT-15		208+51	HARRISON	
I-94/90	ARROW			15.6
	AND ONLY			20.8
			TOTAL	73

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKING- LINE 8" (FOOT)
MOT-02		2638+00	75+94	
I-94/90	WHITE			309
MOT-03		75+94	87+94	
I-94/90	WHITE			1,901
MOT-04		87+94	99+94	
I-94/90	WHITE			774
MOT-05		99+94	111+94	
I-94/90	WHITE			0
MOT-08		125+39	137+39	
I-94/90	WHITE			2,913
MOT-09		137+39	149+39	
I-94/90	WHITE			935
MOT-10		149+39	161+39	
I-94/90	WHITE			1,660
MOT-13		184+51	196+51	
I-94/90	WHITE			412
MOT-14		196+51	208+51	
I-94/90	WHITE			3,529
	3D-12'S			36
MOT-15		184+51	196+51	
I-94/90	3'D-12'S			78
			TOTAL	12,548

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKING- LINE 12" (FOOT)
MOT-02		2638+00	75+94	
I-94/90	WHITE			6
MOT-03		75+94	87+94	
I-94/90	WHITE			49
MOT-08		125+39	137+39	
I-94/90	WHITE			144
MOT-10		149+39	161+39	
I-94/90	WHITE			331
MOT-13		184+51	196+51	
I-94/90	WHITE			59
MOT-14		196+51	208+51	
I-94/90	WHITE			584
			TOTAL	1,171

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	RAISED REFLECTIVE PVT MARKER (BRIDGE) (EACH)
CPM-03		75+94	87+94	
EB I-94/90	10D-30S			92
CPM-04		87+94	99+94	
WB I-94/90	10D-30S			23
	SOLID			168
	GORE			18
CPM-05		99+94	111+94	
WB I-94/90	10D-30S			84
	GORE			39
	SOLID			14
CPM-06		111+94	125+39	
WB I-94/90	10D-30S			109
	SOLID			13
CPM-07		75+94	87+94	
EB I-94/90	10D-30S			8
CPM-08		125+39	137+39	
WB I-94/90	10D-30S			120
	GORE			39
CPM-09		137+39	149+39	
WB I-94/90	10D-30S			120
	GORE			26
CPM-10		149+39	161+39	
WB I-94/90	10D-30S			103
	GORE			16
	GORE			11
	3'-12'			11
CPM-11		161+39	173+25	
WB I-94/90	10D-30S			98
	GORE			11
	3'-12'			20
CPM-12		173+25	184+51	
WB I-94/90	10D-30S			116
	SOLID			33
			TOTAL	1,292

BOWMAN, BARRETT & ASSOCIATES INC
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

CSCH-03

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)

SB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS

CIVIL SCHEDULES

SCALE: NTS DRAWN BY: RA

DATE: 5/12/2006 CHECKED BY: RS

n:\660\cad\civil\21\SHEETS\660_21CP1SCH01.dgn
9:00:22 AM
5/5/2006