

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	2005-025 RS	LAKE	116	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
• PARK ROADS		IDNR File No. 2-03-025 D91-191-04		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3				
60500050	REMOVING CATCH BASINS	EACH	1	1				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	435	435				
61000215	PORTLAND CEMENT CONCRETE SHOULDERS	SQ YD	70	70				
63200310	GUARDRAIL REMOVAL	FOOT	26		26			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
X0325444	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	FOOT	48	48				
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	563	563				
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	13598	13558	40			
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1665	1665				
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	690	690				
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	299	299				
80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	13		13			
81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1				
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3000		3000			
81700105	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 12	FOOT	3500		3500			
81700115	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 8	FOOT	3500		3500			
81800740	AERIAL CABLE, 3-1/C NO. 8, ALUMINUM, WITH MESSENGER WIRE	FOOT	150		150			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	130		130			
84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	13		13			
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13		13			
88600600	DETECTOR LOOP REPLACEMENT	FOOT	75	75				
A2006616	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E		
* A2016614	TREE, QUERCUS ELLIPSOIDALIS (HILL'S OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5				
X0300247	REMOVE WOOD POST	EACH	30	30				
X0300894	PIPE CULVERT REMOVAL 18"	FOOT	130	130				
X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	40	40				
X0321083	PLASTIC CAR BUMPER	EACH	225	225				
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3				
X0321566	MULCH, SPECIAL	SQ YD	18929	18929				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	25.7	25.7				
X0322720	CAST IRON STEPS	EACH	4		4			
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	3	2	1			
X0323359	WASHING AND CLEANING	L SUM	1	1				
X0323388	TRAFFIC COUNTER	EACH	3	3				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	500		500			
X0324010	SKIRTED STEEL GRATING COVER	EACH	1		1			
X0448400	PIPE CULVERT REMOVAL 12"	FOOT	210	210				
X0795800	COARSE AGGREGATE	TON	24		24			
X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	100.5	100.5				
* X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	19014	18929	85			
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	868	868				
X3550410	BITUMINOUS BASE COURSE SUPERPAVE 7 1/2"	SQ YD	8642	8637	5			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	4762.5	4761	1.5			
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	614.5	613	1.5			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1680	1680				
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
X7240500	RELOCATE EXISTING SIGNS	EACH	20	20				
XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	66		66			
XX002093	REMOVAL OF EXISTING RIPRAP	SQ YD	232		232			

1/24/2006

* SPECIALTY ITEMS

Rev. 2-28-06

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
NORTH POINT MARINA

PLOT DATE: 1/24/2006