

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL						
				20 % STATE		15% STATE / 5% CITY	25%STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY
				I000	J000	Y031-IF	Y046	SFTY-1B	Y031-3D	Y060
		URBAN								
				Quantity	Quantity	Quantity	Quantity	Quantity	Quantity	Quantity
• 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	218	218						
• 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	453	453						
• 20100500	TREE REMOVAL, ACRES	ACRE	1.00	1.00						
20200100	EARTH EXCAVATION	CU YD	13,268	13,268						
20200200	ROCK EXCAVATION	CU YD	75	75						
20800150	TRENCH BACKFILL	CU YD	1,799	1799						
• 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	4,374	4374						
• 25000210	SEEDING CLASS 2A	ACRE	2.48	2.48						
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	223.1	223.1						
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	223.1	223.1						
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	223.1	223.1						
• 25100115	MULCH, METHOD 2	ACRE	2.48	2.48						
• 25100630	EROSION CONTROL BALNKET	SO YD	7,614	7,614						
• 25200100	SODDING	SO YD	1,835	1,835						
• 25200200	SUPPLEMENTAL WATERING	UNIT	16.5	16.5						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,480	2,480						
28000300	TEMPORARY DITCH CHECKS	EACH	25	25						
28000400	PERIMETER EROSION BARRIER	FOOT	1,945	1,945						
28000500	INLET AND PIPE PROTECTION	EACH	6	6						
28100107	STONE RIPRAP, CLASS A4	SO YD	201	201						

• SPECIALITY ITEM
 + NON PARTICIPATING ITEM

PLT DATE = Mon Apr 03 11:49:07 2006
 FILE NAME = D:\p\05\11\28262602\1128262602.dgn
 PLOT SCALE = 1/8" = 1' / IN.
 USER NAME = jrdmhd