

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL							
				20 % STATE		15% STATE / 5% CITY	25% STATE / 75% CITY	50% STATE / 50% CITY	100% CITY	100% RRWRD	
				BITUMINOUS	CONCRETE	SIGNAL INSTALATION	MULTI-USE PATHWAY	SIDEWALK	EVP	SANITARY	
				I000	J000	Y031-1F	Y046	SFTY-1B	Y031-3D	Y060	
28200200	FILTER FABRIC	SQ YD	119	119							
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	15,255	15,255							
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	1,450	1,450							
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	1,750	1,750							
35100100	AGGREGATE BASE COURSE, TYPE A	TON	2,379	2,379							
35101400	AGGREGATE BASE COURSE, TYPE B	TON	434			434					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30.8	29.3		1.5					
40600300	AGGREGATE (PRIME COAT)	TON	26	26							
40600895	CONSTRUCTING TEST STRIP	EACH	1	1							
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	672	494		178					
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	729		729						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6,973					6,973			
• 42400800	DETECTABLE WARNINGS	SQ FT	58	58							
44000100	PAVEMENT REMOVAL	SQ YD	11,558	11,558							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	714	714							
44000300	CURB REMOVAL	FOOT	107	107							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,102	4,102							
44000600	SIDEWALK REMOVAL	SQ FT	2,790	2,790							
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	231	231							
44004000	PAVED DITCH REMOVAL	FOOT	235	235							

- SPECIALITY ITEM
- + NON PARTICIPATING ITEM

PLOT DATE \* Mon Apr 03 11:49:47 2006  
 FILE NAME \* C:\projects\p250502\405002.dgn  
 PLOT SCALE \* 50.0000 \* / IN.  
 USER NAME \* jordanhd