

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 742 (IL 2)	40-M	Winnebago	165	15
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64820				

The Contractor shall maintain at least one access point to the trail/mobile home park at all times.

Between 2710 and 2720 South Main Street on the east side of IL 2, there is a sanitary manhole at an unknown location. The manhole will be located and adjusted as needed. The work of locating manhole shall be included in the cost of SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID.

Two weeks prior to the start of construction activities, the Contractor shall place in operation changeable message sign(s) at locations determined by the Engineer.

The Contractor will be required to obtain a sanitary service abandonment permit from Rock River Water Reclamation District (RRWRD) for buildings being removed. There is no charge for the permit, but issuance of the permit is required by Rock River Water Reclamation District and an inspection will be required by RRWRD. Any cost incurred in obtaining the permit shall be included in the cost of BUILDING REMOVAL NO.1, 2, 3, 4, 5, 6, 7.

It shall be the Contractor's responsibility to contact the municipality to determine approved methods of utility structure adjustment. Utility structures may include but are not limited to manholes, water valves, hand holes, etc. All materials and work necessary to complete adjustments per municipality requirements shall be considered included in the cost of the associated adjustment pay item.

Access shall be maintained at all times for Klehm Arboretum located on Clifton Avenue. When the entrances are replaced, they shall be constructed one at a time and one-half at a time.

Proposed inlets or manholes within roadway or entrance areas that will remain open to traffic prior to installation of final pavement shall be covered with a precast reinforced flat slab top or steel plate until such time that the grates or lids can be installed. This work shall not be paid for separately, but shall be included in the contract unit price per Each for the associated drainage structure.

The Contractor may not disturb any areas outside of the proposed construction limits at the Klehm Arboretum property, nor shall the temporary easement on this property be utilized for storage of equipment or materials with the following exceptions:

- The metal storm sewer pipe to be removed at STA 31+25 Lt. 50' shall be removed and paid for as Earth Excavation.
- The concrete storm sewer pipe to be removed at STA 31+85 Lt. 75' shall be removed as Storm Sewer Removal.
- The disturbed area from storm sewer removal shall be graded, shaped and seeded. This work shall be included in the cost of the applicable removal pay item.

COMMITMENTS:

Klehm Arboretum shall be allowed two (2) weeks from the start of the project to remove Klehm Arboretum sign and adjacent landscaping located at Station 342+00 left. The Engineer shall contact Steve Courtney at 815/965-8155 with the project start date.