CONTRACT NO. 64820

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION		OFFSET (FT)	REMARKS
	IL 2			
1.0	LT	336+60.00	69.0	
1.0	LT	337+50.00	63.0	
1.0	LT	339+11.00	55.0	
1.0	LT	340+26.00	54.0	
1.0	LT	341+75.00	52.9	
1.0	LT	344+22.00	82.6	INLET IN NW RETURN
TOTAL 6.0				

28100107 STONE RIPRAP CLASS A4

SQ YD	LOCATION		REMARKS
	IL 2		
82.0	RT	340+00.00	DOWNSTREAM END OF BOX CULVERT
118.9	LT	341+40.00	UPSTREAM END OF BOX CULVERT
TOTAL 200.9			

28200200 FILTER FABRIC

SQ YD	LOCATION		REMARKS
	IL 2		
82.0	RT	340+00.00	DOWNSTREAM END OF BOX CULVERT
118.9	LT	341+40.00	UPSTREAM END OF BOX CULVERT
TOTAL 200.9			

31100925 SUB-BASE GRANULAR MATERIAL, TYPE A 18"

SQ YD	LOCATION	REMARKS
1450	ENTIRE PROJECT	USED AT ENGINEERS DISCRETION
TOTAL 1450.0		ESTIMATED UNDERCUTS

31100965 SUB-BASE GRANULAR MATERIAL, TYPE A 24"

SQ YD	LOCATION	REMARKS
1750	ENTIRE PROJECT	USED AT ENGINEERS DISCRETION
TOTAL 1750.0		ESTIMATED UNDERCUTS

42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH

SQ. YD.	LOCATION		REMARKS
	IL2		
61.3	LT	332+85.67	
69.8	RT	346+92.35	
29.0	LT	347+29.50	
29.8	LT	348+01.00	
94.4	RT	348+35.74	
32.8	LT	348+69.13	
63.1	RT	349+40.94	
55.1	LT	349+40.98	
	COMMERCIAL ENTRANCE		
131.4	LT	11+59.72	
162.1	LT	12+44.88	
TOTAL 728.74			

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

SQ. FT.	LOCATION				REMARKS
	IL 2				
47.3	LT	343+04.62	TO	343+12.3	SW QUAD OF CLIFTON AVE
1543.0	LT	344+27.10	TO	347+23.3	
289.5	LT	347+31.67	TO	347+91.6	
271.0	LT	348+05.44	TO	348+61.1	
251.2	LT	348+72.78	TO	349+25.6	
506.0	LT	349+54.30	TO	350+58.2	
150.0	RT	342+97.29	TO	343+06.7	SE QUAD OF COMMERCIAL ENTRANCE
1313.0	RT	344+03.10	TO	346+74.7	
572.7	RT	347+10.03	TO	348+27.2	
404.5	RT	348+47.72	TO	349+29.0	
588.1	RT	349+52.96	TO	350+71.6	
	CLIFTON AVE				
1036.0	RT	30+50.00	TO	32+34.7	
TOTAL 6,972.3					

42400800 DETECTABLE WARNINGS

SQ. FT.	LOCATION				REMARKS
	IL 2				
20.0	LT	343+09.43	TO	343+16.4	SIDEWALK RAMPS
13.0	RT	343+03.77	TO	343+13.2	SIDEWALK RAMPS
15.0	RT	344+03.84	TO	344+11.4	SIDEWALK RAMPS
10.0	LT	344+25.22	TO	344+29.6	SIDEWALK RAMPS
TOTAL 58.0					

44000100 PAVEMENT REMOVAL

SQ. YD.	LOCATION				REMARKS
	IL 2				
2506.0	LT / RT	332+66.71	TO	337+00.00	
2894.0	LT / RT	337+00.00	TO	342+00.00	
2933.0	LT / RT	342+00.00	TO	347+00.00	
2045.0	LT / RT	347+00.00	TO	350+50.00	
	CLIFTON AVE				
1180.0	LT / RT	30+50.00	TO	32+54.00	
TOTAL 11,558.0					

44000200 DRIVEWAY PAVEMENT REMOVAL

SQ. YD.	LOCATION				OFFSET	REMARKS
	IL 2					
175.0	LT	342+25.00				ABANDONED PARK ENTRANCE
44.0	LT	343+66.04				
31.0	LT	344+00.00				
34.0	LT	347+36.80				
38.0	LT	348+07.34				
13.0	LT	348+74.02				
26.0	LT	349+46.00				
	CLIFTON AVE					
353.0	LT	30+50.00	TO		32+43.00	PAULIE'S PUB PARKING LOT
TOTAL 714.0						

44000300 CURB REMOVAL

EOOT	LOCATION				REMARKS
	IL 2				
85.0	RT	341+75.35	TO	342+65.91	RT/GAS STATION
22.0	RT	342+36.77	TO	342+57.33	RT/GAS STATION
TOTAL 107.0					

44000500 COMBINATION CURB AND GUTTER REMOVAL

EOOT	LOCATION				REMARKS
	IL 2				
970.0	LT	332+66.71	TO	342+21.85	
791.0	LT	343+17.10	TO	350+47.28	
1,771.0	RT	332+66.71	TO	346+59.45	
	CLIFTON AVE				
272.0	RT	30+50.00	TO	32+76.64	
178.0	LT	30+50.00	TO	32+10.40	
120.0	RT/LT	32+44.66	TO	32+80.43	ISLAND
TOTAL 4,102.0					

44000600 SIDEWALK REMOVAL

SQ FT	LOCATION				REMARKS
	IL 2				
826.0	LT	343+07.90	TO	344+23.05	SECTION OF RETURN
187.0	LT	347+42.71	TO	347+98.76	
200.0	LT	348+16.52	TO	348+65.73	
923.0	LT	348+84.24	TO	350+54.04	
14.0	RT	349+19.50	TO	349+23.15	
	CLIFTON AVE				
640.0	LT	31+52.55	TO	32+40.67	SECTION OF RETURN
TOTAL 2,790.0					

44001205 BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE

SQ YD	LOCATION				REMARKS
115.5		332+46.7	TO	332+66.70	
115.5		350+50.0	TO	350+70.00	
TOTAL 231.0					

44004000 PAVED DITCH REMOVAL

EOOT	LOCATION				REMARKS
	IL 2				
113.0	LT	337+85.00	TO	338+93.60	
122.0	LT	339+14.40	TO	340+32.32	
TOTAL 235.0					

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

EOOT				
426.0	LT & RT	332+66	TO	334+80
500.0	LT & RT	348+00	TO	350+50
TOTAL 926.0				

50100100 REMOVAL OF EXISTING STRUCTURES

EACH	LOCATION		REMARKS
	IL 2		
1.0	LT	337+73.60	3' x 2' reinforced box culvert
1.0	LT	339+04.00	3' x 2' reinforced box culvert
TOTAL 2.0			

51000305 PIPE HANDRAIL, SPECIAL

EOOT	LOCATION				REMARKS
	IL2				
70.0	RT	339+75.0	TO	340+45.00	SHOP DRAWINGS REQUIRED
TOTAL 70.0					

PLOT DATE = Fri May 26 13:44:41 2006
FILE NAME = c:\pwworking\dot\d0620802\d0620802rr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = jo-dorhd

SCHEDULE OF QUANTITIES