

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ITEM NO.	DESCRIPTION	QUANTITY	LOCATION	REMARKS
56100600	WATERMAIN 6" FOOT	32.0	LOCATION	REMARKS
TOTAL				
56100700	WATERMAIN 8" FOOT	495.0	LOCATION	REMARKS
TOTAL				
56101000	WATERMAIN 16" FOOT	1095.0	LOCATION	REMARKS
TOTAL				
56400500	FIRE HYDRANTS TO BE REMOVED EACH	2.0	35' RT 33' LT	REMARKS WATERMAIN WATERMAIN
TOTAL				
60107600	PIPE UNDERDRAINS 4" FOOT		LOCATION	REMARKS
		74.0	IL 2	
		74.0	LT/RT	334+12.50 TO 334+12.50
		86.0	LT/RT	336+62.00 TO 336+62.00
		86.0	LT/RT	339+12.50 TO 339+12.50
		30.0	RT	341+75.00 TO 341+75.00
		57.0	LT	344+88.00 TO 344+88.00
		30.0	RT	345+08.00 TO 345+08.00
		30.0	LT	347+38.00 TO 347+38.00
		30.0	LT	347+58.00 TO 347+58.00
		65.0	LT/RT	349+19.50 TO 349+23.15
		29.0	RT	30+89.00 TO 30+89.00
		29.0	LT	31+00.00 TO 31+00.00
TOTAL		590.0		
60255500	MANHOLES TO BE ADJUSTED EACH	5.0	LOCATION	REMARKS
		1.0	IL2	
		1.0	RT	339+02.6 WATER
		1.0	LT	339+32.5 WATER
		1.0	LT	339+76.4 WATER
		1.0	LT	344+28.8 WATER
		1.0	RT	347+11.3 WATER
TOTAL		5.0		
60265700	VALVE VAULT TO BE ADJUSTED EACH	2.0	39' RT 39' LT	REMARKS WATERMAIN WATERMAIN
TOTAL				
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE EACH	5.0	LOCATION	REMARKS
		1.0	IL2	
		1.0	RT	335+71.20
		1.0	RT	337+75.63
		1.0	RT	339+81.63
		1.0	RT	346+17.28
		1.0	RT	348+05.79
TOTAL		5.0		PRIOR TO STAGE 1 TRAFFIC PRIOR TO STAGE 1 TRAFFIC PRIOR TO STAGE 1 TRAFFIC PRIOR TO STAGE 1 TRAFFIC PRIOR TO STAGE 1 TRAFFIC
60500040	REMOVING MANHOLES EACH	12.0	LOCATION	REMARKS
		1.0	IL2	
		1.0	RT	333+66.0 STORM SEWER
		1.0	RT	335+71.6 STORM SEWER
		1.0	RT	337+74.8 STORM SEWER
		1.0	RT	339+81.4 STORM SEWER
		1.0	RT	340+28.0 STORM SEWER
		1.0	RT	340+88.1 STORM SEWER
		1.0	RT	341+77.8 STORM SEWER
		1.0	RT	343+37.4 STORM SEWER
		1.0	RT	343+79.6 STORM SEWER
		1.0	RT	345+36.6 STORM SEWER
		1.0	RT	346+16.9 STORM SEWER
		1.0	RT	348+36.0 STORM SEWER
TOTAL		12.0		
60500060	REMOVING INLETS EACH	18.0	LOCATION	REMARKS
		1.0	IL 2	
		1.0	LT	333+64.50
		1.0	RT	333+65.00
		1.0	RT	335+71.00
		1.0	LT	337+58.20
		1.0	RT	337+75.00
		1.0	RT	339+80.00
		1.0	LT	341+65.00
		1.0	RT	341+75.00
		1.0	RT	343+80.00
		1.0	LT	344+15.00
		1.0	RT	346+18.00
		1.0	LT	346+39.00
		1.0	RT	348+37.00
		1.0	LT	348+38.80
		1.0	LT	348+40.00
		1.0	RT	CLIFTON AVE 31+28.00
		1.0	RT	31+74.80
		1.0	RT	31+74.80
TOTAL		18.0		
60600095	CLASS SI CONCRETE (OUTLET) CU YD	6.0	LOCATION	REMARKS
		6.0	IL 2	
TOTAL		6.0		12+90.00 TO 13+00.00 COMMERCIAL ENTRANCE
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 FOOT	1835.0	LOCATION	REMARKS
		326.5	IL 2	
		895.0	LT	334+17.00 TO 337+32.00 MEDIAN
		467.0	RT	334+17.00 TO 343+05.00 MEDIAN
		146.5	LT	344+08.00 TO 348+73.00 MEDIAN
		146.5	RT	347+33.00 TO 348+73.00 MEDIAN
TOTAL		1835.0		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 FOOT	4,550.5	LOCATION	REMARKS
		1,143.0	IL 2	
		585.0	LT	332+66.71 TO 31+71.68 CLIFTON AVE RETURN
		702.0	LT	337+32.00 TO 343+05.00 MEDIAN
		1,106.0	RT	31+26.25 TO 350+47.28 CLIFTON AVE RETURN
		332.5	RT	332+66.71 TO 11+18.56 COMMERCIAL ENTRANCE RETURN
		682.0	RT	344+08.00 TO 347+33.00 MEDIAN
		682.0	RT	10+95.49 TO 350+47.28 COMMERCIAL ENTRANCE RETURN
TOTAL		4,550.5		
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 FOOT	286.0	LOCATION	REMARKS
		286.0	CLIFTON AVE	
		286.0	LT/RT	30+50.00 TO 32+19.00 MEDIAN
TOTAL		286.0		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 FOOT	202.0	LOCATION	REMARKS
		74.0	CLIFTON AVE	
		128.0	LT	30+50.00 TO 31+26.25
		128.0	RT	30+50.00 TO 31+71.68
TOTAL		202.0		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH SQ FT	8055.0	LOCATION	REMARKS
		6309.0	IL 2	
		1289.0	LT/RT	334+80.00 TO 339+54.00
		1289.0	LT/RT	346+35.00 TO 348+20.00
		457.0	CLIFTON AVE	
		457.0	LT/RT	30+50.00 TO 32+12.23
TOTAL		8055.0		
60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL) SQ FT	4379.0	LOCATION	REMARKS
		430.0	IL 2	
		2188.0	LT/RT	334+17.00 TO 334+80.00
		1451.0	LT	339+54.00 TO 342+98.00
		310.0	RT	344+14.00 TO 346+35.00
		310.0	LT/RT	348+20.00 TO 348+68.00
TOTAL		4379.0		
60624600	CORRUGATED MEDIAN SQ FT	833.0	LOCATION	REMARKS
		416.0	IL 2	
		417.0	LT/RT	333+31.00 TO 334+80.00
		417.0	LT/RT	348+05.05 TO 349+54.03
TOTAL		833.0		

PLOT DATE = Fri May 26 13:44:41 2006  
 FILE NAME = c:\pwork\meta\p205082\p205082.dwg  
 PLOT SCALE = 50.0000 / IN  
 USER NAME = jordanp