63200310 GUARDRAIL REMOVAL

EOOT	LOCATION				REMARKS
	IL 2				
78.0	LT	337+98.65	TO	338+73.95	
90.0	LT	337+64.44	TO	337+82.58	
86.0	RT	339+62.78	TO	340+50.35	
TOTAL 254.0					

66410400 CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED

EOOT	LOCATION		REMARKS
	IL 2		
80.0	LT	341+40.00	UPSTREAM END OF BOX CULVERT
TOTAL 80.0			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION		REMARKS
1.0	DETERMINED BY ENGINEER	APPROX 350+00	CAST-IN-PLACE
1.0	DETERMINED BY ENGINEER	APPROX 341+00	CAST-IN-PLACE
TOTAL 2.0			

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

EOOT	LOCATION				REMARKS
YELLOW	IL 2				
	STAGE 1				
4150.0	RT	329 + 91.7	TO	350 + 50.0	CENTERLINE
750.0	RT	351 + 25.0	TO	354 + 97.0	CENTERLINE
WHITE					
1825.0	RT	314 + 41.7	TO	332 + 66.7	SB TAPER AREA/RT EDGE LINE
1789.0	RT	332 + 66.7	TO	350 + 50.0	SB RT EDGE LINE
50.0	RT	351 + 16.3	TO	351 + 72.3	SB RT EDGE LINE
875.0	RT	351 + 72.0	TO	359 + 97.0	TAPER AREA/SB RT EDGE LINE
YELLOW	STAGE 2				
1450.0	LT	325 + 41.7	TO	332 + 66.7	CENTERLINE
3590.0	LT	332 + 66.7	TO	350 + 50.0	CENTERLINE
370.0	LT	351 + 16.0	TO	352 + 97.0	CENTERLINE
750.0	LT	352 + 97.0	TO	357 + 97.0	NB TAPER AREA/LT EDGE LINE
WHITE					
1825.0	LT	314 + 41.7	TO	332 + 66.7	TAPER AREA/NB RT EDGE LINE
450.0	LT	332 + 66.7	TO	337 + 00.0	NB RT EDGE LINE
750.0	LT	343 + 00.0	TO	350 + 50.0	NB RT EDGE LINE
270.0	LT	344 + 30.0	TO	347 + 00.0	SB RIGHT TURN LANE
56.0	LT	351 + 16.3	TO	351 + 72.3	SB RT EDGE LINE
TOTAL 18,950.0					

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				REMARKS
	IL 2				
	STAGE 2 A				
275.0		351+75.00	TO	360+00.00	
	STAGE 2				
466.7		318+91.00	TO	332+66.00	
283.3		324+25.00	TO	332+66.00	
TOTAL 1,025.0					

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION		OFFSET (FT)	REMARKS
	IL 2			
15.6	RT	339+53.24	41.5	RT TURN ARROW
15.6	RT	340+35.23	41.5	RT TURN ARROW
15.6	RT	340+35.84	1.0	LT TURN ARROW
15.6	RT	341+17.23	41.5	RT TURN ARROW
15.6	RT	341+18.72	1.0	LT TURN ARROW
15.6	RT	341+99.22	41.5	RT TURN ARROW
15.6	RT	342+01.00	1.0	LT TURN ARROW
15.6	RT	342+84.46	1.0	LT TURN ARROW
15.6	LT	344+28.67	1.0	LT TURN ARROW
15.6	LT	344+35.15	41.0	RT TURN ARROW
15.6	LT	344+78.31	1.0	LT TURN ARROW
15.6	LT	344+78.31	41.0	RT TURN ARROW
15.6	LT	345+27.96	1.0	LT TURN ARROW
15.6	LT	345+27.96	41.0	RT TURN ARROW
15.6	LT	345+77.57	1.0	LT TURN ARROW
	CLIFTON AVE			
26.0	RT	31+21.60	15.0	RT/THROUGH TURN ARROW
15.6	RT	31+21.60	2.5	LT TURN ARROW
26.0	RT	31+96.34	15.0	RT/THROUGH TURN ARROW
15.6	RT	31+96.34	2.5	LT TURN ARROW
TOTAL 317.2				

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

EOOT	LOCATION				REMARKS
YELLOW	IL 2				
558.0		332 + 31.0	TO	334 + 09.7	CENTERLINE, DOUBLE YELLOW
608.0		348 + 75.	TO	350 + 66.8	CENTERLINE, DOUBLE YELLOW
	CER+41				
345.0		10 + 73.0	TO	12 + 43.0	FLUSH MEDIAN
SUBTOTAL 1511.0					
WHITE	IL 2				
410.0	NB RT	332 + 66.7	TO	336 + 77.4	EDGE LINE
424.0	SB LT	332 + 66.7	TO	336 + 91.7	EDGE LINE
260.0	NB RT	332 + 66.7	TO	343 + 05.4	SKIP DASH
260.0	SB LT	332 + 66.7	TO	343 + 05.4	SKIP DASH
280.0	NB RT	347 + 73.4	TO	350 + 52.9	EDGE LINE
280.0	SB LT	347 + 70.0	TO	350 + 52.9	EDGE LINE
160.0	NB RT	344 + 08.9	TO	350 + 47.3	SKIP DASH
160.0	SB LT	344 + 08.9	TO	350 + 47.3	SKIP DASH
SUBTOTAL 2,234.0					
TOTAL 3,745.0					

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

EOOT	LOCATION				REMARKS
WHITE	IL 2				
38.50	RT	343 + 07.4	TO	343 + 23.1	CROSSWALK SE QUADRANT
129.00	RT	343 + 30.5	TO	344 + 01.5	CROSSWALK
160.33	LT/RT	344 + 05.6	TO	344 + 02.8	CROSSWALK
59.50	LT	344 + 00.0	TO	344 + 26.7	CROSSWALK NW QUADRANT
155.60	LT	343 + 13.2	TO	343 + 91.3	CROSSWALK
TOTAL 542.9					

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

EOOT	LOCATION				REMARKS
WHITE	IL 2				
56.00	NB	337 + 32.5	TO	339 + 32.5	TURKEY TRACKS
363.00	NB	339 + 32.5	TO	343 + 04.9	RT TURN LANE
56.00	NB	338 + 15.9	TO	340 + 13.9	TURKEY TRACKS
588.00	NB	340 + 13.9	TO	343 + 06.4	LT TURN LANE
77.50	SB	343 + 88.2	TO	344 + 39.1	ISLAND
390.00	SB	344 + 06.6	TO	345 + 97.9	LT TURN LANE
34.00	SB	345 + 97.9	TO	347 + 28.0	TURKEY TRACKS
149.00	SB	344 + 08.9	TO	345 + 53.0	RT TURN LANE
50.00	SB	345 + 53.0	TO	347 + 28.0	TURKEY TRACKS
	SB		TO		
	CLIFTON AVE				
12.00	LT	30 + 50.0	TO	31 + 01.6	TURKEY TRACKS
18.00	RT	30 + 50.0	TO	31 + 01.6	TURKEY TRACKS
117.00	RT	31 + 01.6	TO	32 + 16.3	LT TURN LANE
	CER+41				
48.00	RT	10 + 75.0	TO	11 + 23.0	LEFT TURN LANE
26.00	RT	11 + 23.0	TO	11 + 97.5	TURKEY TRACKS
TOTAL 1,984.5					

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

EOOT	LOCATION				REMARKS
YELLOW	CER+41				
41.00		11 + 23.0	TO	12 + 43.0	DIAGONALS FOR FLUSH MEDIAN
SUBTOTAL 41.00					
WHITE	IL 2				
124.00	NB	332 + 66.7	TO	336 + 77.5	DIAGONALS FOR PAINTED EDGE
131.00	SB	332 + 66.7	TO	336 + 91.7	DIAGONALS FOR PAINTED EDGE
53.00	NB	340 + 13.9	TO	343 + 06.4	DIAGONALS FOR LEFT TURN LANE
111.00	SB	343 + 88.2	TO	344 + 39.1	DIAGONALS FOR PAINTED ISLANDS
38.00	SB	344 + 06.6	TO	345 + 97.9	DIAGONALS FOR LEFT TURN LANE
49.00	NB	347 + 73.4	TO	350 + 52.9	DIAGONALS FOR PAINTED EDGE
48.00	SB	347 + 70.0	TO	350 + 47.3	DIAGONALS FOR PAINTED EDGE
SUBTOTAL 554.00					
TOTAL 595.0					

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

EOOT	LOCATION		REMARKS
	IL 2		
12.00	NB	343 + 04.4	STOP BAR LT TURN LANE
24.00	NB	343 + 04.4	STOP BAR THROUGH LANES
21.00	NB	343 + 11.1	STOP BAR RT TURN LANE
12.00	SB	344 + 06.6	STOP BAR LT TURN LANE
24.00	SB	344 + 06.6	STOP BAR THROUGH LANES
18.00	SB	344 + 16.8	STOP BAR RT TURN LANE
	CLIFTON AVE		
39.00	RT	32 + 16.3	STOP BAR LT TURN/THROUGH LANE
	CER+41		
35.00	LT	10 + 73.0	STOP BAR LT TURN/THROUGH LANE
TOTAL 185.0			

PLOT DATE = Fri May 26 13:44:42 2006
FILE NAME = c:\projects\2050802\d050802sv.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = jpcdavid

SCHEDULE OF QUANTITIES