

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	40-M	WINNEBAGO	165	89
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE	ITEM	UNIT	TOTAL
#2001379	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	1295
80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1
81400400	CONCRETE HANDHOLE	EACH	8
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1496
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1275
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1311
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2399
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	913
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	107
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FOOT	EACH	2
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT	EACH	1
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT	EACH	1
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT	EACH	1
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	27.75

PAY CODE	ITEM	UNIT	TOTAL
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	29.5
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	535
X0324886	CONDUIT INSTALLED, 1 1/4", NON-METALLIC	FOOT	75
X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	139
X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	375
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8
X880395	SIGNAL HEAD, POLYCARDONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
X8810395	PEDESTRAIN SIGNAL HEAD, POLYCARDONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2
X8810495	PEDESTRAIN SGNAL HEAD, POLYCARDONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2
X8880010	ADA PEDESTRIAN PUSH-BUTTON	EACH	6
XX003162	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	1
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1

CLIFTON AVE. MAST ARM ASSEMBLY FOUNDATIONS

MAST ARM LENGTH	FOUNDATION (DIA.)	MIN. DEPTH	MIN. CAGE LENGTH
28'	30"	13.75'	13.25'
34'	30"	14.00'	13.50'
44'	36"	14.50'	14.00'
55'	36"	15.00'	14.50'

PLOT DATE = Fri May 26 14:07:17 2006  
 FILE NAME = C:\pwork\cva\2055002\ds05002-eaf.dgn  
 PLOT SCALE = 28.0000 / IN.  
 USER NAME = jordanad