

SUMMARY OF QUANTITIES

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	21T	STEPHENSON	49	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	ROADWAY Y007
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1
54010502	PRECAST CONCRETE BOX CULVERT 5' X 2'	FOOT	120
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	60
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	42
542ID018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	36
54213453	END SECTIONS 18"	EACH	2
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	10
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	384
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	30
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67100100	MOBILIZATION	L. SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	122
Z0005400	BREAKER-RUN CRUSHED STONE	TON	174
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1
Z0017100	DOWEL BARS	EACH	144
Z0029001	GRATED CULVERT EXTENSION, NO. 1	EACH	2
Z0029002	GRATED CULVERT EXTENSION, NO. 2	EACH	2
A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3
X0301794	INLET, STAND PIPE	EACH	1
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	43

*SPECIALTY ITEMS

FILE NAME = #FILE#
 LEVELS = #LEVELS#
 DATE = #DATE#
 PLOT DATE = #PLOT DATE#
 OPERATOR = #OPERATOR#
 REF = #REF#
 REF = #REF#
 REF = #REF#