

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28BR-1	JO DAVIESS	54	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

70400100 TEMPORARY CONCRETE BARRIER

EQUI	LOCATION	ION	LOCATION
708	US 20 LT&RT 1431+03 - 1438+12	16	US 20 RT 1429+61 - 1433+13
708	TOTAL	15	LT 1430+18 - 1433+13

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

EQUI	LOCATION	ION	LOCATION
708	US 20 LT&RT 1431+03 - 1438+12 STAGE I	13	LT&RT 1432+93 - 1433+13
708	LT&RT 1431+03 - 1438+12 STAGE II	13	LT&RT 1436+01 - 1436+21
1416	TOTAL	7	RT 1436+01 - 1437+70

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

EQUI	LOCATION	ION	LOCATION
585	US 20 STA. 1428+01 - 1439+72 (YELLOW SKIP DASH)	1	US 20 RT 1431+04
1200	RT 1431+58 - 1437+58 (WHITE EDGE LINE)	1	RT 1438+12
1200	LT 1431+61 1437+61 (WHITE EDGE LINE)	2	TOTAL
2985	TOTAL		

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	ION	LOCATION
4	US 20 RT 1429+02 - 1433+13	1	US 20 LT 1431+04
4	LT 1430+55 - 1433+13	1	LT 1438+12
4	RT 1436+01 - 1437+35	2	TOTAL
4	LT 1436+01 - 1438+73		
16	TOTAL		

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	ION	LOCATION
1	US 20 RT 1429+02	1	US 20 LT 1431+04
1	LT 1430+55	1	LT 1438+12
1	RT 1437+35	2	TOTAL
1	LT 1438+73		
4	TOTAL		

78300500 PAINT PAVEMENT MARKING REMOVAL

SO FT	LOCATION	ION	LOCATION
34	US 20 STA. 1428+01 - 1432+00 (YELLOW SKIP DASH)	1	US 20 RT 1431+04
66	STA. 1428+01 - 1430+00 (YELLOW NO PASSING)	1	LT 1438+12
421	RT 1428+01 - 1440+64 (WHITE EDGE LINE)	2	TOTAL
421	LT 1428+01 - 1440+64 (WHITE EDGE LINE)		
31	STA. 1437+00 - 1440+64 (YELLOW SKIP DASH)		
973	TOTAL		

X4066426 BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX D, N70

EACH	LOCATION	ION	LOCATION
1	US 20 RT 1431+04	16	US 20 RT 1429+61 - 1433+13
1	RT 1438+12	15	LT 1430+18 - 1433+13
2	TOTAL	13	LT&RT 1432+93 - 1433+13

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	ION	LOCATION
1	US 20 RT 1431+04	13	LT&RT 1432+93 - 1433+13
1	RT 1438+12	13	LT&RT 1436+01 - 1436+21
2	TOTAL	7	RT 1436+01 - 1437+70

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	ION	LOCATION
1	US 20 LT 1431+04	11	US 20 LT 1436+01 - 1439+06
1	LT 1438+12	75	TOTAL
2	TOTAL		

PLOT DATE = Thu Mar 30 07:52:35 2006
 PLOT SCALE = 50.000000
 USER NAME = mesj11

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY