

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	141-1 M	OGLE	73	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	TOTAL	90% FEDERAL	90% FEDERAL
				10% STATE ROADWAY J000-1A	10% STATE SIGNALS Y031-1F
20200100	EARTH EXCAVATION	CU. YD.	1220	1220	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ. YD.	150	150	
25100630	EROSION CONTROL BLANKET	SQ. YD.	793	793	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250	
28000400	PERIMETER EROSION BARRIER	FOOT	1862	1862	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ. YD.	2176	2176	
31100920	SUB-BASE GRANULAR MATERIAL, TYPE A, 15"	SQ. YD.	150	150	
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A, 18"	SQ. YD.	150	150	
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A, 24"	SQ. YD.	150	150	
40600990	TEMPORARY RAMP	SQ. YD.	85	85	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT, 10" (JOINTED)	SQ. YD.	2291	2291	
44000008	BITUMINOUS SURFACE REMOVAL, 2 1/2"	SQ. YD.	2572	2572	
44000100	PAVEMENT REMOVAL	SQ. YD.	846	846	
44002805	ISLAND REMOVAL	SQ. FT.	94	94	
44003700	MEDIAN REMOVAL (SPECIAL)	SQ. FT.	715	715	
44004250	PAVED SHOULDER REMOVAL	SQ. YD.	1381	1381	
44200970	CLASS B PATCHES, TYPE II, 10 "	SQ. YD.	79	79	

PLOT DATE = Thu Mar 20 14:50:45 2008
 FILE NAME = I:\Users\mrb005\Documents\64B37.dgn
 PLOT SCALE = 50.0000' / 1" IN.
 USER NAME = dssadd