

# SUMMARY OF QUANTITIES

CONTRACT NO. 64B37				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	141-1 M	OGLE	73	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(IL 38)				

CODE NUMBER	ITEM	UNITS	TOTAL	90% FEDERAL	90% FEDERAL
				10% STATE ROADWAY J000-1A	10% STATE SIGNALS Y031-1F
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1
89502380	REMOVE EXISTING HANDHOLE	EACH	2		2
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2		2
X0322674	STROBE LIGHT	EACH	2		2
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	426		426
X0324885	CONDUIT INSTALLED, 1", NON-METALLIC	FOOT	446		446
X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	68		68
X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	203		203
X0656300	PAVEMENT REMOVAL & REPLACEMENT	SQ YD	3		3
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	166	166	
X4066438	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	231	231	
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	144	144	
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	<b>3</b>		<b>3</b>
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7		7
X8801350	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1		1
XX002267	MEDIAN REMOVAL & REPLACEMENT	SQ FT	34		34
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	1	
Z0017100	DOWEL BARS	EACH	120	120	

\*SPECIALTY ITEMS

PLOT DATE = Thu Mar 30 14:08:15 2006  
 PLOT SCALE = 50.0000 / 1"  
 USER NAME = dmsadd