

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*567	141-1 M	OGLE	73	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

## SCHEDULE OF QUANTITIES

### 28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	REMARKS
250	Entire Job	
250	TOTAL	

### 31100920 SUB-BASE GRANULAR MATERIAL, TYPE A, 15'

SQ YD	LOCATION	REMARKS
150.0	As Conditions Dictate	At the discretion of the Engineer

### 28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	REMARKS
<i>IL 38</i>		
312.0	LT Sta. 668+60.0 TO 671+72.0	
40.0	LT Sta. 673+20.0 TO 673+60.0	
<i>N.B. On Ramp</i>		
220.0	RT Sta. 10+40.0 TO 12+40.0	
770.0	LT Sta. 10+44.9 TO 18+15.8	
<i>N.B. Off Ramp</i>		
520.0	LT Sta. 117+59.3 TO 122+54.4	
1862.0	TOTAL	

### 31100935 SUB-BASE GRANULAR MATERIAL, TYPE A, 18'

SQ YD	LOCATION	REMARKS
150.0	As Conditions Dictate	At the discretion of the Engineer

### 31100965 SUB-BASE GRANULAR MATERIAL, TYPE A, 24'

SQ YD	LOCATION	REMARKS
150.0	As Conditions Dictate	At the discretion of the Engineer

### 28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET (ft)	REMARKS
1	LT <i>N.B. On Ramp</i>	17+00	48.0
1	TOTAL		EXISTING CULVERT

### 40600990 TEMPORARY RAMP

SQ YD	LOCATION	REMARKS
17.8	<i>N.B. Off Ramp</i>	
17.8	Sta. 117+59.3 TO 117+69.3	
17.8	Sta. 121+14.4 TO 121+24.4	
17.8	<i>N.B. On Ramp</i>	
32.0	Sta. 18+05.3 TO 18+15.3	
85.4	Sta. 11+06.1 TO 11+16.1	
85.4	TOTAL	

### 31100910 SUB-BASE GRANULAR MATERIAL, TYPE A, 12'

SQ YD	LOCATION	REMARKS
<i>IL 38</i>		
29.4	LT Sta. 671+18.4 TO 671+58.3	
393.0	LT Sta. 668+89.3 TO 671+72.4	
27.0	LT Sta. 671+00	Base for new median surface and CCC&G
<i>N.B. Off Ramp</i>		
13.7	RT Sta. 122+40	Removed raised island
446.1	LT Sta. 117+59.3 TO 122+54.4	
<i>N.B. On Ramp</i>		
848.2	LT Sta. 10+35.1 TO 18+15.8	
405.8	RT Sta. 10+35.1 TO 12+34.3	
<i>Drain for Aggregate Base Course</i>		
<i>IL 38</i>		
1.3	LT Sta. 669+00	
1.3	LT Sta. 671+60	
1.3	LT Sta. 673+50	
<i>N.B. Off Ramp</i>		
1.3	LT Sta. 117+60	
1.3	LT Sta. 120+00	
1.3	LT Sta. 122+25	
<i>N.B. On Ramp</i>		
1.3	RT Sta. 11+00	
1.3	LT Sta. 12+50	
1.3	LT Sta. 15+00	
1.3	LT Sta. 16+90	
2176.2	TOTAL	

### 42000500 PORTLAND CEMENT CONCRETE PAVEMENT, 10" (JOINTED)

SQ YD	LOCATION	REMARKS
<i>IL 38</i>		
43.0	LT Sta. 671+18.4 TO 671+58.3	Replaces removed median
205.0	LT Sta. 668+89.3 TO 671+72.4	
<i>N.B. Off Ramp</i>		
95.0	LT Sta. 117+59.3 TO 119+79.3	Widening
265.0	LT Sta. 119+79.3 TO 122+54.4	Widening
231.1	RT Sta. 121+24.4 TO 122+54.4	Main Line 16' Width
190.8	RT Sta. 121+51.5 TO 122+54.4	Right Turn Lane
91.6	RT Sta. 121+16.6 TO 122+54.4	Triangle
<i>N.B. On Ramp</i>		
519.0	LT Sta. 10+35.1 TO 13+44.2	Widening
276.0	LT Sta. 13+44.2 TO 18+15.8	Widening
375.0	RT Sta. 10+35.1 TO 12+34.3	Widening
144.0	LT Sta. 10+35.1 TO 11+16.1	Main Line 16' Width
129.2	RT Sta. 10+35.1 TO 11+16.1	Right Turn Lane
59.3	RT Sta. 10+35.1 TO 10+66.3	Triangle
2291.5	TOTAL	

PLOT DATE = Thu Mar 30 14:27:10 2006  
 FILE NAME = c:\p\projects\6210005\dl0005.plt.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = dmsadd