

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*567	141-1 M	OGLE	73	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

44000008 BITUMINOUS SURFACE REMOVAL 2 1/2"

SQ YD	LOCATION	REMARKS
959.4	N.B. Off Ramp Sta. 117+59.3 TO 121+50	Ramp and Rt. Shoulder
186.5	N.B. On Ramp Sta. 11+30 TO 12+34.9	Ramp Only
1426.4	Sta. 12+34.9 TO 18+15.8	Ramp and Rt. Shoulder
<u>2572.3</u>	TOTAL	

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION	REMARKS
231.1	N.B. Off Ramp RT Sta. 121+24.40 TO 122+54.4	Main Line 16' Width
190.8	RT Sta. 121+51.5 TO 122+54.4	Right Turn Lane
91.6	RT Sta. 121+16.6 TO 122+54.4	Triangle
144.0	N.B. On Ramp LT Sta. 10+35.1 TO 11+16.1	Main Line 16' Width
129.2	RT Sta. 10+35.1 TO 11+16.1	Right Turn Lane
59.3	RT Sta. 10+35.1 TO 10+66.3	Triangle
<u>846.0</u>	TOTAL	

44002805 ISLAND REMOVAL

SQ FT	LOCATION	REMARKS
94.0	RT Sta. 122+40	
<u>94.0</u>	TOTAL	

44003700 MEDIAN REMOVAL (SPECIAL)

SQ FT	LOCATION	REMARKS
715.0	LT Sta. 670+82 TO 671+52	Median nose = 9' thick, remainder of median = 6' thick
<u>715.0</u>	TOTAL	

44004250 PAVED SHOULDER REMOVAL

SQ. YD.	LOCATION	REMARKS
370.1	IL 38 LT Sta. 668+61.4 TO 671+94.5	
72.0	LT Sta. 672+95.5 TO 673+59.3	
156.7	N.B. On Ramp RT Sta. 10+35.2 TO 12+34.4	
385.0	LT Sta. 10+35.2 TO 18+15.8	
269.4	N.B. Off Ramp LT Sta. 117+59.3 TO 122+54.4	
127.3	RT Sta. 121+24.4 TO 122+54.4	
<u>1380.5</u>	TOTAL	

44200970 CLASS B PATCHES TYPE II, 10'

SQ. YD.	LOCATION	REMARKS
8.0	IL 38 LT Sta. 669	W.B. Inside Lane, 6'
8.0	LT Sta. 669	W.B. Outside Lane, 6'
8.0	LT Sta. 669	W.B. Inside Lane, 6'
8.0	LT Sta. 670	W.B. Outside Lane, 6'
8.0	LT Sta. 671	W.B. Outside Lane, 6'
8.0	LT Sta. 671	W.B. Inside Lane, 6'
7.4	LT Sta. 671	N. Intersection Pavement, 6'
8.0	LT Sta. 671	S. Intersection Pavement, 6'
8.0	LT Sta. 671	E.B. inside Lane, 6'
8.0	LT Sta. 671	E.B. Outside Lane, 6'
<u>79.4</u>	TOTAL	

44200974 CLASS B PATCHES TYPE III, 10'

SQ. YD.	LOCATION	REMARKS
18.7	IL 38 LT Sta. 669	W.B. Outside Lane, 12'
16.0	LT Sta. 670	W.B. Outside Lane, 14'
<u>34.7</u>	TOTAL	

44213100 PAVEMENT FABRIC

SQ. YD.	LOCATION	REMARKS
18.7	IL 38 LT Sta. 669	W.B. Outside Lane, 12'
16.0	LT Sta. 670	W.B. Outside Lane, 14'
<u>34.7</u>	TOTAL	

44213200 SAW CUTS

FEET	LOCATION	REMARKS
42.0	IL 38 TYPE II LT Sta. 669	W.B. Inside Lane, 6' Long, 12" Wide
42.0	LT Sta. 669	W.B. Outside Lane, 6' Long, 12" Wide
42.0	LT Sta. 669	W.B. Inside Lane, 6' Long, 12" Wide
42.0	LT Sta. 670	W.B. Outside Lane, 6' Long, 12" Wide
42.0	LT Sta. 671	W.B. Outside Lane, 6' Long, 12" Wide
42.0	LT Sta. 671	W.B. Inside Lane, 6' Long, 12" Wide
39.0	LT Sta. 671	N. Intersection Pavement, 6' Long, 11' Wide
42.0	LT Sta. 671	S. Intersection Pavement, 6' Long, 12' Wide
42.0	LT Sta. 671	E.B. inside Lane, 6' Long, 12' Wide
42.0	LT Sta. 671	E.B. Outside Lane, 6' Long, 12' Wide
48.0	IL 38 TYPE III LT Sta. 669	W.B. Outside Lane, 12' Long, 12' Wide
50.0	LT Sta. 670	W.B. Outside Lane, 14' Long, 12' Wide
<u>515.0</u>	TOTAL	

PLOT DATE = Thu Mar 30 14:27:18 2006
 FILE NAME = c:\p\projects\210005\cl10005.dgn
 PLOT SCALE = 50.0000 * / IN.
 USER NAME = dmsd