

F.A.P. RY.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*567	141-1 M	OGLE	73	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

## 44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FEET	LOCATION	REMARKS
781.4	<i>N.B. Off Ramp</i> Sta. 117+59.3 TO 121+50	Lt & Rt. E.O.P. @ Shoulder Joint
390.7	Sta. 117+59.3 TO 121+50	
1371.6	<i>N.B. On Ramp</i> Sta. 11+30 TO 18+15.8	Lt & Rt. E.O.P. @ Shoulder Joint
685.8	Sta. 11+30 TO 18+15.8	
<b>3229.5</b>	<b>TOTAL</b>	

## 78008200 POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS

SQ. FT.	LOCATION	OFFSET (ft)	REMARKS
<i>White</i>	<i>IL 38</i>		
26	Sta 661 + 2		LT Turn & Thru Arrow
26	Sta 662 + 68		LT Turn & Thru Arrow
26	Sta 664 + 34		LT Turn & Thru Arrow
26	Sta 666 + 0		LT Turn & Thru Arrow
26	Sta 667 + 66		LT Turn & Thru Arrow
26	Sta 669 + 31		LT Turn & Thru Arrow
26	Sta 670 + 13		LT Turn & Thru Arrow
26	Sta 670 + 94		LT Turn & Thru Arrow
11.5	Sta 669 + 31		Thru Arrow
11.5	Sta 670 + 13		Thru Arrow
11.5	Sta 670 + 94		Thru Arrow
<u>23</u>	Sta 674 + 0		Reinstall Merge Rt. Arrow
<b>265.5</b>	<b>SUB TOTAL</b>		

## 48202310 BITUMINOUS SHOULDERS SUPERPAVE. 5 1/2"

SQ. YD.	LOCATION	REMARKS
350.0	<i>IL 38</i> LT Sta. 668+61.4 TO 671+72.4	10' width
28.6	LT Sta. 673+21.4 TO 673+59.3	10' Tapering to 4' width
91.1	<i>N.B. On Ramp</i> RT Sta. 10+42.0 TO 12+05.2	4' width
14.8	RT Sta. 12+05.2 TO 12+34.3	4' tapering to 8' width
345.0	LT Sta. 10+44.9 TO 18+15.8	4' width
228.7	<i>N.B. Off Ramp</i> LT Sta. 117+59.3 TO 122+54.4	4' width (includes 10' wide portion on IL 38)
127.3	RT Sta. 121+24.4 TO 122+54.4	
<b>1185.5</b>	<b>TOTAL</b>	

<i>N.B. Off Ramp</i>			
15.6	Sta 120 + 15		LT Turn Arrow
15.6	Sta 120 + 78		LT Turn Arrow
15.6	Sta 121 + 40		LT Turn Arrow
15.6	Sta 122 + 3		LT Turn Arrow
31.2	Sta 120 + 15		LT Turn & RT Turn Arrow
31.2	Sta 120 + 78		LT Turn & RT Turn Arrow
31.2	Sta 121 + 40		LT Turn & RT Turn Arrow
<u>31.2</u>	Sta 122 + 3		LT Turn & RT Turn Arrow
<b>187.2</b>	<b>SUB TOTAL</b>		

## 60620000 CONCRETE MEDIAN, TYPE SB - 6.24

SQ. FT.	LOCATION	REMARKS
465.0	<i>IL 38</i> LT Sta. 670+82 TO 671+25	
<b>465.0</b>	<b>TOTAL</b>	

429.7 TOTAL

## 70300520 PAVEMENT MARKING TAPE, TYPE III, 4"

FOOT	LOCATION	REMARKS
1600.0	<i>IL 38</i> LT Sta. 667+50 TO 683+50	
1200.0	RT Sta. 667+50 TO 679+50	
775.0	<i>N.B. On Ramp</i> Sta. 10+50 TO 18+25	
650.0	<i>N.B. Off Ramp</i> Sta. 116+00 TO 122+50	
<b>4225.0</b>	<b>TOTAL</b>	

## 78008210 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"

FOOT	LOCATION	REMARKS
<i>Yellow</i>	<i>RAMPS</i>	
754	Sta 10+35 To 18+16	NB Entrance Ramp EOP
485	Sta 117+61 To 122+54	NB Exit Ramp EOP
<b>1239</b>	<b>SUB TOTAL</b>	
<i>White</i>	<i>IL 38</i>	
305	Sta 668+89 To 671+94	WB EOP
70	Sta 668+61 To 671+11	WB CL Dash
854	Sta 10+35 To 18+16	NB Entrance Ramp EOP
557	Sta 117+61 To 122+54	NB Exit Ramp EOP
<u>100</u>	Sta 11+00 To 14+65	NB Entrance Ramp
<b>1886</b>	<b>SUB TOTAL</b>	

## 70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION	REMARKS
533.0	<i>IL 38</i> LT Sta. 667+50 TO 683+50	Type III Tape
400.0	RT Sta. 667+50 TO 679+50	Type III Tape
<b>933.0</b>	<b>TOTAL</b>	

3125 TOTAL

PLOT DATE = Thu Mar 30 14:27:18 2006  
 PLOT SCALE = 50.0000 / 1 IN.  
 USER NAME = dbasdd