

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*567	141-1 M	OGLE	73	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

Location	Earth Excavation (Cut) (Cu Yd)	Earth Excavation Adjusted for Shrinkage (Cu Yd)	Embankment (Fill) (Cu Yd)	Earthwork Balance Waste (+) Shortage (-) (Cu Yd)
IL 38				
668+75 - 673+50	291	218	66	152
Northeast Ramp				
10+75 - 18+00	638	478	502	-24
Southeast Ramp				
117+75 - 122+50	291	218	72	146
TOTAL	1219	915	640	274

DATE-TIME
 DRAWN-SPEC
 REF
 REF
 REF