CONTRACT NO. 64C26

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
316	101TS	LEE	9	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN
Y031-1F
90% FED.
5% STATE
5% CITY

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNIT	TOTAL
X0325339	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	97
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
* 72000100	SIGN PANEL TYPE I	SQ FT	15
* 72000200	SIGN PANEL TYPE II	SQ FT	25
80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1
81400400	CONCRETE HANDHOLE	EACH	3
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1490
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTIBLE POWER SUPPLY	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2047
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	798
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	120
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FOOT	EACH	2
87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT	EACH	1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT	EACH	1
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT	EACH	1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	15.5
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	50.5
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10
X0300737	RADIO TRANSCEIVER	EACH	1
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	514
X0324887	CONDUIT INSTALLED, 2 1/2", NON-METALLIC	FOOT	162
X0324888	CONDUIT INSTALLED, 4", NON-METALLIC	FOOT	347
* X7800580	POLYUREA PAVEMENT MARKING, SPECIAL, LINE 24"	FOOT	162
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
X8801395	SIGNAL HEAD, POLYCARDONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Thu Mar 30 07:48:07 2006
FILE NAME = P:\Projects\BLOODY GULCH 64C26\the il 26.BG plans.dgn
PLOT SCALE = 20.0000 ' / IN.
USER NAME = hillki