

FAS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2402	(113B-2)	PEORIA	55	8

STA.	TO STA.
FED. ROAD DIST. NO.	US 150

LOCATION	EARTH EXCAVATION (CU YD)	FOR INFORMATION ONLY				TOPSOIL FURNISH AND PLACE, 4" (SQ YD)	EARTH EXCAVATION (WIDENING) (CU YD)
		EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	FURNISHED EXCAVATION (SQ YD)		
STA.309+00 TO 309+50	27.0	20.3	136.0	-115.7	-115.7	313.9	
STA.309+50 TO 310+00	29.2	21.9	114.8	-92.9	-92.9	345.6	
STA.310+00 TO 310+50	2.2	1.7	45.0	-43.3	-43.3	200.2	
BRIDGE OMISSION							
STA.312+50 TO 313+00	34.8	26.1	166.8	-140.7	-140.7	300.3	
STA.313+00 TO 313+50	75.7	56.8	64.1	-7.3	-7.3	350.0	
STA.313+50 TO 314+38	46.7	35.1	145.3	-110.2	-110.2	612.6	
STA.314+38 TO 314+50	3.2	2.4	40.2	-37.8	-37.8	83.1	
STA.314+50 TO 315+00	5.7	4.3	80.6	-76.3	-76.3	173.6	
STA 308+00 to 310+25							33.3
STA 312+65 to 315+30							39.3
TOTAL	224.5	168.6	792.8	-624.2	-624.2	2379	72.6

LOCATION

LOCATION	REMOVAL LENGTH (FOOT)	GUARDRAIL MARKER TYPE A (EACH)	EROSION CONTROL CURB (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 6A (EACH)	GUARDRAIL AGGRAGATE EROSION CONTROL (TON)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) (EACH)	TERMINAL MARKER DA (EACH)
LT STA. 308+73 - 310+25					22.2			
LT STA. 312+64 - 313+60			96		14.0			
LT STA. 314+14 - 315+26			112		16.3			
RT STA. 309+29 - 310+85					14.0			
RT STA. 312+64 - 314+25			221		32.2			
LT STA. 308+73 - 313+60		7						
LT STA. 314+14 - 315+26		4						
RT STA. 309+29 - 314+85		8						
LT STA. 309+29 - 310+28	99							
LT STA. 312+60 - 313+83	123							
LT STA. 314+18 - 315+30	112							
RT STA. 309+29 - 310+28	99							
RT STA. 312+62 - 314+15	153							
LT STA. 309+17 - 310+00						85		
LT STA. 312+88 - 313+10.5						22.5		
LT STA. 314+64 - 314+76.5						12.5		
RT STA. 309+79.5 - 310+02						22.5		
RT STA. 312+88 - 314+35.5						147.5		
LT STA. 310+00 - 310+30				1				
LT STA. 312+58 - 312+88				1				
RT STA. 310+00 - 310+30				1				
RT STA. 312+58 - 312+88				1				
LT STA. 308+73 - 309+23							1	
LT STA. 314+76.5 - 315+26.5							1	
LT STA. 313+10.5 - 313+60.5							1	
LT STA. 314+14 - 314+64							1	
RT STA. 309+29.5 - 309+79.5							1	
RT STA. 314+35.5 - 314+85.7							1	
LT STA. 308+73								1
LT STA. 313+60								1
LT STA. 314+14								1
LT STA. 315+26								1
RT STA. 309+29								1
RT STA. 314+85								1
TOTAL	586	19	429	4	99	290	6	6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: NO SCALE DRAWN BY: MAJ
DATE: CHECKED BY: