

SUMMARY OF QUANTITIES

MCDONOUGH COUNTY
80% FEDERAL / 20% STATE

CONSTRUCTION TYPE CODE

ROADWAY RURAL
← I000-2A →

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY RURAL			Y030-1E LIGHTING	BRIDGES X181-5B SN 055-0052, 0053 BRIDGES OVER RAILROAD	BRIDGES X641-5B SN 055-9901 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9902 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9903 RR BRIDGES OVER ROADWAY	BRIDGES X081-2A SN 055-0060, 0061 WILDLIFE BRIDGES	CULVERTS X028-2A SN 055-2501, 2502, 2503 CAST IN PLACE CULVERTS
				(BIT.)	(A-3)	(AGG)							
51203500	TEST PILE STEEL HP10X57	EACH	2										
51203600	TEST PILE STEEL HP12X53	EACH	4										
51203610	TEST PILE STEEL HP12X63	EACH	2										
51203800	TEST PILE STEEL HP14X73	EACH	11										
51204315	CONCRETE ENCASEMENT	CU YD	224										
51204600	METAL SHOES	EACH	216										
51500100	NAME PLATES	EACH	10										
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2	2									
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	2	2									
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	2	2									
54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH	2	2									
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	2	2									
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	2	2									
54001007	BOX CULVERT END SECTION, CULVERT NO.7	EACH	2	2									
54001010	BOX CULVERT END SECTION, CULVERT NO.10	EACH	2	2									
54001011	BOX CULVERT END SECTION, CULVERT NO.11	EACH	2	2									
54001012	BOX CULVERT END SECTION, CULVERT NO.12	EACH	2	2									
54001014	BOX CULVERT END SECTION, CULVERT NO.14	EACH	2	2									
54003000	CONCRETE BOX CULVERTS	CU YD	1,725										1,725
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	192	192									
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	72	72									
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	357	357									
54010606	PRECAST CONCRETE BOX CULVERT 6' X 6'	FOOT	588	588									
54010807	PRECAST CONCRETE BOX CULVERT 8' X 7'	FOOT	587	587									
54010808	PRECAST CONCRETE BOX CULVERT 8' X 8'	FOOT	314	314									
54010905	PRECAST CONCRETE BOX CULVERT 9' X 5'	FOOT	300	300									
54011007	PRECAST CONCRETE BOX CULVERT 10' X 7'	FOOT	388	388									
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	65	65									
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	163	118	45								
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	729	729									

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06

DRAWN BY
CHECKED BY