

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	MCDONOUGH	1025	13
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				MCDONOUGH COUNTY 80% FEDERAL / 20% STATE										
				ROADWAY RURAL			CONSTRUCTION TYPE CODE							
				(BIT.)	(A-3)	(AGG)	Y030-1E LIGHTING	BRIDGES X181-5B SN 055-0052, 0053 BRIDGES OVER RAILROAD	BRIDGES X641-5B SN 055-9901 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9902 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9903 RR BRIDGES OVER ROADWAY	BRIDGES X081-2A SN 055-0060, 0061 WILDLIFE BRIDGES	CULVERTS X028-2A SN 055-2501, 2502, 2503 CAST IN PLACE CULVERTS	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY											
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	101	101										
54201477	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	28	28										
54201483	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	58	58										
54201489	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	64	64										
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	11	5	4	2								
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	49	45	4									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	16	8	8									
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	6	6										
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	6	4	2									
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	5	5										
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	2			2								
54215460	CAST-IN-PLACE REINFORCED CONCRETE END SECTION 60"	EACH	2	2										
54215466	CAST-IN-PLACE REINFORCED CONCRETE END SECTION 66"	EACH	2	2										
54215472	CAST-IN-PLACE REINFORCED CONCRETE END SECTION 72"	EACH	2	2										
54215547	METAL END SECTIONS 12"	EACH	12	12										
54215550	METAL END SECTIONS 15"	EACH	2		2									
54215553	METAL END SECTIONS 18"	EACH	35	35										
54215556	METAL END SECTIONS 21"	EACH	2		2									
54215559	METAL END SECTIONS 24"	EACH	14	8	6									
54215565	METAL END SECTIONS 30"	EACH	6	2	4									
54215571	METAL END SECTIONS 36"	EACH	2	2										
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	1	1										
54218506	REINFORCED CONCRETE PIPE TEE, 72" PIPE WITH 36" RISER	EACH	1	1										
5422C024	PIPE CULVERTS, CLASS C, TYPE 2 24" (TEMPORARY)	FOOT	119	119										
5422D018	PIPE CULVERTS, CLASS D, TYPE 2 18" (TEMPORARY)	FOOT	50	50										
5422D024	PIPE CULVERTS, CLASS D, TYPE 2 24" (TEMPORARY)	FOOT	50	50										
5422D036	PIPE CULVERTS, CLASS D, TYPE 2 36" (TEMPORARY)	FOOT	60	60										
54223015	REINFORCED CONCRETE PIPE TEE, SPECIAL	EACH	1	1										
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2	2										
54244805	INLET BOX STANDARD 542501	EACH	1	1										

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06
DRAWN BY
CHECKED BY

2006-06-27 10:00 AM