

SUMMARY OF QUANTITIES

MCDONOUGH COUNTY
80% FEDERAL / 20% STATE

CONSTRUCTION TYPE CODE

ROADWAY RUF
← I000-2A →

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY RUF			Y030-1E LIGHTING	BRIDGES X181-5B SN 055-0052, 0053 BRIDGES OVER RAILROAD	BRIDGES X641-5B SN 055-9901 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9902 RR BRIDGES OVER ROADWAY	BRIDGES X641-5B SN 055-9903 RR BRIDGES OVER ROADWAY	BRIDGES X081-2A SN 055-0060, 0061 WILDLIFE BRIDGES	CULVERTS X028-2A SN 055-2501, 2502, 2503 CAST IN PLACE CULVERTS
				(RT)	(A-3)	(AGG)							
* 72600100	MILE POST MARKER ASSEMBLY	EACH	16	16									
* 73000100	WOOD SIGN SUPPORT	FOOT	3,915	3,915									
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47									
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	19,896	19,896									
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	191,026	191,026									
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	854	854									
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	5,923	5,923									
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	213	213									
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	292	292									
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,190	5,190									
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,260	1,260									
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	14					8				6	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	78	65	13								
78200520	BARRIER WALL MARKERS, TYPE B	EACH	12	12									
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	17	9	8								
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	4				4						
* 80803150	WOOD LIGHTING POLE, 55 FT, CLASS 3	EACH	12				12						
* 81020500	CONDUIT PUSHED, 2" DIA INTERMEDIATE METAL	FOOT	620				620						
* 81020700	CONDUIT PUSHED, 3" DIA INTERMEDIATE METAL	FOOT	120				120						
* 81500200	TRENCH & BACKFILL FOR ELECTRICAL WORK	FOOT	3,200				3,200						
* 81600215	UD 2# 8 XLP, 1# 8 XLPG 3/4" P	FOOT	935				935						
* 81600315	UD 2# 6 XLP, 1# 6 XLPG 1" P	FOOT	3,570				3,570						
* 81800600	AERIAL CABLE, 2-1/C#2, ALUMINUM, V MESSENGER WIRE	FOOT	2,350				2,350						
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	30				30						
* 82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	4				4						
* 83054100	LIGHT POLE, STEEL GALVANIZED, 45' M.H., TENON MOUNT	EACH	6				6						
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8" X 6"	EACH	6				6						
* 83600357	LIGHT POLE FOUNDATION, METAL, 15" B.C., 8" X 8"	EACH	6				6						
* 83800650	BREAKAWAY DEVICE, COUPLING, SS SCREEN	EACH	48				48						
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	12				12						

* SPECIALTY ITEMS

⊙ SFTY-3C

REVI. NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06
DRAWN BY
CHECKED BY