

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	44
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

PERMANENT SURVEY MARKER SCHEDULE			
LOCATION	PERMANENT SURVEY MARKERS, TYPE I	PERMANENT SURVEY MARKERS, TYPE II	PERMANENT SURVEY TIES
STATION	EACH	EACH	EACH
IL RTE. 336			
STA. 128+00.00		1	4
STA. 139+91.36	1		4
STA. 149+00.00		1	4
STA. 158+44.61		1	4
STA. 164+64.43		1	4
STA. 186+45.44		1	4
STA. 171+41.36		1	4
STA. 183+80.44	1		4
STA. 191+50.00		1	4
STA. 199+22.01		1	4
STA. 204+14.16		1	4
STA. 214+00.00		1	4
STA. 224+00.00		1	4
STA. 231+00.00		1	4
STA. 237+80.74	1		4
STA. 248+00.00		1	4
STA. 258+00.00		1	4
STA. 268+00.00		1	4
STA. 274+00.00		1	4
STA. 280+19.20		1	4
STA. 297+14.57		1	4
STA. 303+50.00		1	4
STA. 310+29.15		1	4
STA. 322+47.43		1	4
STA. 324+52.20	1		4
STA. 333+00.00		1	4
STA. 341+00.00		1	4
STA. 349+72.20	1		4
STA. 356+93.10		1	4
STA. 367+00.00		1	4
STA. 376+71.26	1		4
STA. 387+12.05		1	4
STA. 396+50.96		1	4
STA. 405+14.44	1		4
STA. 415+00.00		1	4
STA. 425+00.00		1	4
STA. 434+00.00		1	4
STA. 438+65.92		1	4
STA. 464+05.51		1	4
STA. 470+75.00	1		4
STA. 480+37.41		1	4
STA. 504+38.45		1	4
STA. 514+50.00		1	4
STA. 524+50.00		1	4
STA. 534+50.00		1	4
STA. 542+00.00		1	4
STA. 549+51.09		1	4
STA. 573+85.04		1	4
S.N. 055-0052	1		4
S.N. 055-0053	1		4
S.N. 055-2501	1		4
S.N. 055-2502	1		4
S.N. 055-2503	1		4
S.N. 055-0060	1		4
S.N. 055-0061	1		4
S.N. 055-9901	1		4
S.N. 055-9902	1		4
S.N. 055-9903	1		4
TOTAL	18	40	232

RUNAROUND SCHEDULE						
LOCATION	AGGREGATE BASE COURSE, TYPE A 8"	AGGREGATE BASE COURSE, TYPE B 8"	INCIDENTAL BITUMINOUS SURFACING	BITUMINOUS BASE COURSE SUPERPAVE	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70
LOCATION	SQ YD	SQ YD	TON	TON	TON	TON
U.S. ROUTE 136						
STA. 202+80.00	TO	STA. 219+33.00				
			3,526.0	34.0	593.0	395.0
TWP. RD. 118						
STA. 14+39.86	TO	STA. 23+96.50	2,551.0		429.0	286.0
SUBTOTAL			2,551.0	3,526.0	1,022.0	286.0
TOTAL			2,551	3,526	1,022	286

CONVERSION RATES
 ASPHALT: 112 LB/SQ YD IN
 AGGREGATE = 2.05 TON/CU YD
 0.004 TONS = GALLON

TEMPORARY CONCRETE BARRIER SCHEDULE					
LOCATION					TEMPORARY CONCRETE BARRIER (STATE OWNED)
U.S. ROUTE 136 TEMPORARY RUN-AROUND					FOOT
STA. 206+79	LT	TO	STA. 210+00	LT	320
STA. 206+90	RT	TO	STA. 210+00	RT	310
STA. 210+00	RT	TO	STA. 213+20	RT	320
STA. 210+00	LT	TO	STA. 215+51	LT	550
U.S. ROUTE 136 (IL. ROUTE 336 STATIONING)					
STA. 130+00	RT	TO	STA. 139+00	RT	900
STA. 139+00	RT	TO	STA. 142+24	RT	320
TOTAL					2,720

IMPACT ATTENUATORS SCHEDULE			
LOCATION		IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW) TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, WIDE) TEST LEVEL 3
STATION	LT/RT	EACH	EACH
IL RTE. 136			
STA. 130+00	RT	1	
STA. 142+24	RT	1	
STA. 206+79	LT		1
STA. 206+90	RT	1	
STA. 213+20	RT	1	
STA. 215+51	LT		1
TOTAL		4	2

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES IL. ROUTE 336
NAME	DATE	
DATE 3/30/06		DRAWN BY CHECKED BY