

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	47
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SIGNING SCHEDULE (CONTINUED)						
LOCATION		SIGN CODE	MESSAGE OR DESCRIPTION	SIGN PANEL -	SIGN PANEL -	WOOD SIGN SUPPORT
				TYPE 1	TYPE 2	
				SQ FT	SQ FT	FOOT
TR 118						
19+00	RT	R6-1 (LT) (36X12)	ONE WAY	3.00		20
		R6-1 (RT) (36X12)	ONE WAY	3.00		
		R1-1 (36)	STOP	9.00		
		R6-3 (24X18)	DIVIDED HIGHWAY	3.00		
21+00	LT	R6-1 (LT) (36X12)	ONE WAY	3.00		20
		R6-1 (RT) (36X12)	ONE WAY	3.00		
		R1-1 (36)	STOP	9.00		
		R6-3 (24X18)	DIVIDED HIGHWAY	3.00		
26+00	LT	W3-1 (30)	STOP AHEAD	6.25		17
TR 194						
49+00	RT	R6-1 (RT) (36X12)	ONE WAY	3.00		20
		R1-1 (30)	STOP	6.25		
		R6-3a (24X18)	DIVIDED HIGHWAY	3.00		
OLD TR 200 (STA 50 + 35)	(LT)	OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TR 200 RELOCATED						
43+00	RT	W1-4 (30)	REVERSE CURVE (RIGHT)	6.25		20
54+59	RT	W3-1 (30)	STOP AHEAD	6.25		17
59+09	RT	R6-1 (LT) (36X12)	ONE WAY	3.00		20
		R6-1 (RT) (36X12)	ONE WAY	3.00		
		R1-1 (36)	STOP	9.00		
		R6-3 (24X18)	DIVIDED HIGHWAY	3.00		
60+91	LT	R6-1 (LT) (36X12)	ONE WAY	3.00		20
		R6-1 (RT) (36X12)	ONE WAY	3.00		
		R1-1 (36)	STOP	9.00		
		R6-3 (24X18)	DIVIDED HIGHWAY	3.00		
65+50	LT	W3-1 (30)	STOP AHEAD	6.25		17
TR 900N EAST						
100+55	LT	R1-1 (30)	STOP	6.25		17
105+55	LT	W3-1 (30)	STOP AHEAD	6.25		17
TR900 RELOCATED						
72+00	RT	W1-4 L (30)	REVERSE CURVE	6.25		17
85+50	RT	W3-1 (30)	STOP AHEAD	6.25		17
89+27	RT	R1-1 (30)	STOP	6.25		17
TR 226 RELOCATED						
101+00	LT	R6-1 (RT) (36X12)	ONE WAY	3.00		20
		R1-1 (36)	STOP	9.00		
		R6-3a (24X18)	DIVIDED HIGHWAY	3.00		
105+00	LT	W3-1 (30)	STOP AHEAD	6.25		17
106+25	LT	W1-2 (LT) (30)	CURVE	6.25		17
TR 226 CUL-DE-SAC						
		W14-1 (30)	DEAD END	6.25		16
		W8-1108 (30)	ROAD ENDS 500 FT.	6.25		16
		OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TR154 NORTH						
		W14-1 (30)	DEAD END	6.25		16
		W8-1108 (30)	ROAD ENDS 500 FT.	6.25		16
		OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TR 154 SOUTH						
		W14-1 (30)	DEAD END	6.25		16
		W8-1108 (30)	ROAD ENDS 500 FT.	6.25		16
		OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TR 102 NORTH						
		W14-1 (30)	DEAD END	6.25		16
		W8-1108 (30)	ROAD ENDS 500 FT.	6.25		16
		OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TR102 SOUTH						
		W14-1 (30)	DEAD END	6.25		16
		W8-1108 (30)	ROAD ENDS 500 FT.	6.25		16
		OM4-1 (18)	ROAD END MARKER	2.25		12
		R11-1100 (48X30)	ROAD ENDS		10.00	2 @ 14
		OM4-1 (18)	ROAD END MARKER	2.25		12
TOTAL				1486.43	636.25	3,915

Note: Additional Temporary signs as part of the Traffic Control & Protection are NOT listed in this schedule, see M.O. T. sheets

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06

DRAWN BY
CHECKED BY