F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	48
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

TEMPORARY PIPE CULVERT SCHEDULE

LOCATION	INLET AND PIPE PROTECTION	PIPE CULVERTS, CLASS A, TYPE 1 (TEMPORARY)	PIPE CULVERTS, CLASS D, TYPE 1 (TEMPORARY)		PIPE CULVERTS, CLASS C, TYPE 2 (TEMPORARY)	PRECAST REINFORCED CONCRETE FLARED END SECTIONS	PIPE CULVERTS, CLASS D, TYPE 2 (TEMPORARY)			METAL END SECTIONS			PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE
		12"	18"	24"	24"	24"	18"	24"	36"	18"	24"	36"	12"	18"	24"
	EACH	FT	FT	FT	FT	EACH	FT	FT	FT	EACH	EACH	EACH	FT	FT	FT
IL ROUTE 336															
STA. 132+74.00 14.00 FT LT TO STA. 132+80.00 20.00 FT RT	1	36													
STA. 348+68.00 95.40 FT LT TO STA. 349+86.00 93.70 FT LT	1				119	2									
STA. 376+44.00 87.50 FT LT TO STA. 376+94.00 85.90 FT LT	1							50			2				
CROSSOVER															
STA. 25+00.00 23.00 FT LT TO STA. 25+00.00 23.00 FT RT	1		58							2					
TWP. RD. 118 TEMP. RUN AROUND															
STA. 105+50.00 30.00 FT LT TO STA. 105+50.00 30.00 FT RT	1								60			2			
STA. 110+50.00 25.00 FT RT TO STA. 110+50.00 25.00 FT LT	1						50			2					
RAILROAD SHOO-FLY															
STA. 9+00.00 15.00 FT LT TO STA. 9+00.00 15.00 FT RT	1													30	
STA. 23+00.00 16.00 FT LT TO STA. 23+00.00 16.00 FT RT	1														64
STA. 29+38.37 15.00 FT RT TO STA. 29+66.37 15.00 FT RT	1												28		
STA. 29+67.33 12.80 FT LT TO STA. 29+78.68 12.80 FT RT	1													28	
GOLF COURSE ACCESS ROAD															
STA. 37+58.00 78.60 FT RT TO STA. 37+61.00 13.50 FT RT				65											
STA. 55+22.50 84.90 FT RT TO STA. 55+40.00 53.30 FT RT	1			36											
TOTAL	11	36	58	101	119	2	50	50	60	4	2	2	28	58	64

CONSTRUCTION LAYOUT SCHEDULE

LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL	1

POROUS GRANULAR MATERIAL SCHEDULE

LOCATION	POROUS GRANULAR MATERIAL CU YD	FILTER FABRIC SQ YD
IL 336		
LT STA. 175+95 TO RT STA. 176+98	19.7	
RT STA. 212+47 TO LT STA. 214+42	66.7	
RT STA. 240+02 TO LT STA. 242+37	55.0	
LT STA. 252+35 TO RT STA. 254+46	237.1	86.0
LT STA. 275+45 TO RT STA. 276+66	75.1	
SUBTOTAL	453.6	86.0
TOTAL	454	86

* ADDITIONAL MATERIAL REQUIRED FOR ROCK CUT REPLACEMENT AT CULVERTS

CONCRETE MEDIAN SURFACE SCHEDULE

LOCATION	CONCRETE MEDIAN SURFACE, 4 INCH SQ FT	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 FOOT
RAMP I		
STA. 10+42.67 LT TO STA. 10+56.02 LT	70.0	35.0
RAMP J		
STA. 182+09.76 RT TO STA. 182+24.76 RT	97.0	40.0
TOTAL	167	75

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 SCHEDULE

LOCATION	FOOT
RAMP I	
STA. 10+39.51 TO STA. 11+29.86	161
STA. 10+48.58 TO STA. 10+83.37	35
STA. 10+48.58 TO STA. 10+91.06	45
RAMP J	
STA. 181+35.32 TO STA. 182+23.77	167
STA. 181+76.70 TO STA. 182+19.34	44
STA. 181+83.71 TO STA. 182+19.34	37
TOTAL	489

ROCK FILL REPLACEMENT

LOCATION	TON
IL 336	
STA. 199+81.68	99
STA. 213+42.60	126
STA. 301+29.45	230.0
TOTAL	455.0

PAVEMENT MARKING TAPE, TYPE III SCHEDULE

LOCATION	PAVEMENT MARKING TAPE, TYPE III: WHITE EDGE LINE FOOT	YELLOW EDGE LINE FOOT	DOUBLE YELLOW FOOT
IL 336			
RT STA. 128+00 TO RT STA. 130+00	200		
RT STA. 131+00 TO LT STA. 140+25	1,140		
RT STA. 132+85 TO RT STA. 133+85	100		
LT STA. 134+25 TO LT STA. 138+25	400		
RT STA. 131+70 TO RT STA. 132+70		100	
RT STA. 135+70 TO LT STA. 139+70		400	
RT STA. 128+00 TO RT STA. 131+70			740
LT STA. 139+25 TO LT STA. 140+06			200
SUBTOTAL	1,840	500	940
SECOND APP.	1,840	500	940
TOTAL	6,560		

ROCK FILL SCHEDULE

LOCATION	ROCK FILL TON	FILTER FABRIC SQ YD
STA. 519+70.00 RT TO STA. 527+50.00 LT	12,823.0	10,689.0
TOTAL	12,823.0	10,689.0

NOTE: QUANTITY FOR ROCK FILL INCLUDES 6" CAP/CAP MATERIAL TO BE CA-7 OR CA-11 AGGREGATE

SUB-BALLAST SCHEDULE

LOCATION	CU YD
RAILROAD SHOO-FLY	
STA. 4+47.56 TO STA. 37+05.02	2,521.52
TOTAL	2,522

REMOVE EXISTING STRUCTURES

LOCATION	EACH
TR 226	
STA. 104+50	1
TOTAL	1

SHORT-TERM PAVEMENT MARKING SCHEDULE

LOCATION	FOOT
U.S. ROUTE 136 (RELOCATED)	
STA. 1+00.00 TO STA. 32+00.00	310
COUNTY HIGHWAY 8	
STA. 31+00.00 TO STA. 37+50.00	130
STA. 37+79.00 TO STA. 39+00.00	24
TOTAL	464

OPEN-GRADED DRAINAGE BLANKET SCHEDULE

LOCATION	CU YD
IL 336	
STA. 150+30.00 RT TO STA. 155+47.00 LT	13,271
STA. 153+80.00 RT TO STA. 167+32.00 CL	41,777
STA. 299+25.00 RT TO STA. 302+75.00 LT	4,512
STA. 473+38.00 RT TO STA. 479+50.00 CL	17,663
STA. 481+50.00 CL TO STA. 487+37.00 RT	16,858
STA. 491+90.00 RT TO STA. 495+50.00 LT	5,012
STA. 494+38.00 RT TO STA. 498+75.00 LT	5,678
TOTAL	104,771

CONCRETE MEDIAN SCHEDULE

LOCATION	SQ FT
RAMP I	
STA. 10+42.55 TO STA. 10+48.55	168
RAMP J	
STA. 182+19.10 TO STA. 182+25.10	158
TOTAL	326

RAILROAD PROTECTIVE LIABILITY INSURANCE SCHEDULE

LOCATION	RAILROAD PROTECTIVE LIABILITY INSURANCE L SUM
ENTIRE PROJECT	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR SCHEDULE

LOCATION	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR L. SUM
ENTIRE PROJECT	1
TOTAL	1

SETTLEMENT PLATFORMS SCHEDULE

LOCATION	OFFSET	EACH
IL ROUTE 336		
STA. 158+80	CL	1
STA. 159+60	25.0 R	1
STA. 301+00	CL	1
STA. 474+00	CL	1
STA. 485+00	CL	1
STA. 496+50	CL	1
TR 226		
STA 105+00	CL	1
TOTAL		7

VERTICAL PLASTIC WICK DRAINS SCHEDULE

LOCATION	FOOT
STA. 150+53.00 RT TO STA. 155+45.00 LT	57,097.0
STA. 153+80.00 RT TO STA. 159+57.00 LT	64,753.0
TOTAL	121,850.0

TRAINEES SCHEDULE

LOCATION	HOURS
ENTIRE PROJECT	3,000
TOTAL	3,000

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL. ROUTE 336

DATE 3/30/06

DRAWN BY

CHECKED BY

SCHED 314.dgn 5/5/2006 9:25:51 AM