F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	55-2	McDONOUGH	1025	179
STA. 37+00		TO STA. 40+00		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

PLAN
SURVEYED
DRAWN
ALIGNMENT CHECKED
GRADES CHECKED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
DRAWN
GRADES CHECKED
NOTE BOOK
NO.
BY
DATE

CONCORD PROPERTY ASSOCIATES, LLC.

CHAMP AND PAULINE WAYLAND

DELBERT C. MANARD TRUST

JOSEPH E. MANARD, TRUSTEE

PROPOSED ℄ IL. ROUTE 336

MATCH EXISTING PAVEMENT GRADE STA. 38+50.00

MATCH EXISTING PAVEMENT WIDTH AND GRADE STA. 38+28.00

PROPOSED R.O.W./A.C.

CONSTRUCTION LIMITS

EXISTING R.O.W.

END A.C.

PROP. A.C.

EXISTING R.O.W.

PROPOSED A.C.

END A.C.

PROPOSED ℄ CO. HWY. 8 (EAST)

CO. HWY. 8 (650E)

46' TAPER

MATCH EXISTING SHOULDER WIDTH AND GRADE LT. AND RT. STA. 37+78

IL. ROUTE 336

STA. 349+72.20 IL. ROUTE 336 = STA. 40+00.00 CO. HWY. 8

348+00

349+00

350+00

351+00

352+00

37+00

38+00

39+00

SEE INTERSECTION DETAILS FOR FURTHER LAYOUT INFORMATION

N

25 0 50 100

SCALE IN FEET HORIZONTAL

IL. ROUTE 336
STA. 40+00.00

8x = 0.20'
100.00' V.C.

EXISTING ℄ PROFILE

PROPOSED ℄ PROFILE

38+28.00 679.32+ MATCH EXISTING

38+50.00 679.25+ MATCH EXISTING

39+00.00 679.10 VPI EL.

39+50.00 679.76 VPI EL. 679.77

39+61.00 679.95 VPI EL. 679.77

+1.50%

-0.31%

+1.34%

+1.50%

EXISTING ELEVATIONS
PROPOSED ELEVATIONS

	37+00	38+00	39+00	40+00
EXISTING	679.52 679.61 679.62 679.56 679.42 679.33	679.26 679.25 679.20 679.22 679.18 679.30	679.22 679.48 679.16 679.76 679.36 679.77	679.64

710 700 690 680 670 660 650 640 630

SCALE IN FEET VERTICAL 0 5 10 20

ROADWAY PLAN AND PROFILE – CO. HWY. 8 (EAST) – STA. 37+00 TO STA. 40+00

8e-rd01.dgn 3/30/2006 5:24:32 AM