


DESIGNED: RB  
 CHECKED: AMPH  
 DRAWN: AMPH  
 CHECKED: RB



RANDOLPH & ASSOCIATES, INC.  
 41 N. FORTER HIGHWAY, PEORIA, IL 61614-2114  
 TEL: 309-691-9944 FAX: 309-691-9920  
 HTTP://WWW.RANDOLPHINC.COM  
 CONSULTING ENGINEERS • LAND SURVEYORS

FILE NUMBER 136.115	FAU RTE. 6584	SECTION 105R-1	COUNTY PEORIA	TOTAL SHEETS 115	SHEET NO. 6
DATE June 2003	STA.	TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	

100% STATE

SUMMARY OF QUANTITIES (SHEET 2 of 3)

URBAN  
CONSTRUCTION TYPE CODE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				1000-2A	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1009	1009	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	501	501	
44000900	BITUMINOUS CONCRETE REMOVAL	SQ YD	171	171	
44004000	PAVED DITCH REMOVAL	FOOT	292	292	
44004250	PAVED SHOULDER REMOVAL	SQ YD	429	429	
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	66	66	
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	3316	3316	
50105210	REMOVE EXISTING CULVERTS	FOOT	11	11	
50105220	PIPE CULVERT REMOVAL	FOOT	695	695	
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT	18	18	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	1150	1150	
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	127	127	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	201	201	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	67	67	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	106	106	
550A0420	STORM SEWERS, CLASS A, TYPE 2, 27"	FOOT	244	244	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	220	220	
55100400	STORM SEWER REMOVAL 10"	FOOT	20	20	
55100500	STORM SEWER REMOVAL 12"	FOOT	15	15	
55100900	STORM SEWER REMOVAL 18"	FOOT	35	35	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3	3	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4	
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60241900	INLETS, TYPE G-1, SPECIAL	EACH	15	15	
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	
60500060	REMOVING INLETS	EACH	2	2	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	275	275	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3518	3518	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	
66700605	PERMANENT SURVEY TIES	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	

SUMMARY OF QUANTITIES

ALLEN ROAD  
 F.A.U. 6584 (SBI 174) SECTION 105R-1  
 PEORIA COUNTY