


DESIGNED AMPH/RE	 RANDOLPH & ASSOCIATES, INC. 111 W. FLETCHER PARKWAY, PEORIA, IL 61614-1014 TEL. (309) 693-8944 FAX. (309) 693-8945 • 1-800-831-1321 HTTP://WWW.RANDOLPH-ASSOCIATES.COM CONSULTING ENGINEERS • LAND SURVEYORS	FILE NUMBER 136.115	F.A.U. RTE. 6584	SECTION 105R-1	COUNTY PEORIA	TOTAL SHEETS 115	SHEET NO. 14
CHECKED RB		DATE February 2004	STA. TO STA.				
DRAWN AMP		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT					
CHECKED RB							

COMBINATION CURB & GUTTER REMOVAL		
LOCATION STATION TO STATION	LT/RT	LENGTH
		FOOT
ALTORFER DRIVE - C STA. 188+66.47 LT		
STA. 21+72.00 TO STA. 22+21.30 (Radius Return)	LT	59
STA. 21+72.00 TO STA. 22+21.30 (Radius Return)	RT	59
STA. 20+79.00 TO STA. 20+82.80	LT & RT	7.6
FUTURE STREET - C STA. 194+26.20 RT		
STA. 30+33.70 TO STA. 30+60.00 (Radius Return)	RT	46
STA. 30+37.00 TO STA. 30+60.01 (Radius Return)	LT	47
CURB LINING ENTRANCE @ STA. 181+31.20		
STA. 181+31.20	LT	64
CURB LINING ENTRANCE @ STA. 184+03.30		
STA. 184+03.30	LT	68
STA. 193+48.00 TO STA. 193+90.00	LT	51.2
STA. 194+21.00 TO STA. 194+28.00	LT	50.4
STA. 194+56.00 TO STA. 194+96.00	LT	48.8
TOTAL		501.0

BIT. CONCRETE REMOVAL	
LOCATION STATION TO STATION	AREA SQ YD
STA. 178+75.72 LT TO STA. 180+37.70 LT	171.10
TOTAL 171.10	

BIT. SURFACE REMOVAL 2"	
LOCATION STATION TO STATION	AREA SQ YD
STA. 178+89.50 LT TO STA. 180+91.10 LT	148.7
TOTAL 148.7	

PAVED SHOULDER REMOVAL	
LOCATION STATION TO STATION	AREA SQ YD
STA. 178+89.50 LT TO STA. 180+91.10 LT	142.90
STA. 176+60.00 RT TO STA. 180+91.10 RT	286.22
TOTAL 429.12	

BIT. SURFACE REMOVAL 1 1/2"	
LOCATION STATION TO STATION	AREA SQ YD
STA. 176+60.00 RT TO STA. 180+36.10 RT	501.46
TOTAL 501.46	

PAVEMENT REMOVAL	
LOCATION STATION TO STATION	AREA
	SQ YD
ALTORFER DRIVE - C STA. 188+66.47 RT	
STA. 20+79.00 TO STA. 21+31.30	362.2
ALTORFER DRIVE - C STA. 188+66.47 LT	
STA. 21+69.30 TO STA. 22+21.30	199.25
FUTURE STREET - C STA. 194+26.20 RT	
STA. 30+00.00 TO STA. 30+60.00	257.25
TOTAL 818.7	

PAVED DITCH REMOVAL	
LOCATION STATION TO STATION	LENGTH
	FOOT
STA. 180+69.40 LT	18
STA. 180+91.10 LT TO STA. 181+14.25 LT	26
STA. 181+46.00 LT TO STA. 181+70.00 LT	26
STA. 182+70.00 LT	12
STA. 183+67.00 LT TO STA. 183+87.00 LT	23
STA. 184+24.00 LT TO STA. 184+41.00 LT	20
STA. 191+97.00 LT TO STA. 193+65.00 LT	167
TOTAL 292	

BIT. SURFACE REMOVAL - BUTT JOINT	
LOCATION STATION TO STATION	AREA SQ YD
STA. 180+36.10 TO STA. 180+66.10	168
STA. 184+30.84 TO STA. 184+60.84	126.66
STA. 184+77.84 TO STA. 185+07.84	126.66
STA. 196+35.10 TO STA. 196+65.10	219.00
TOTAL 640.32	

DRIVEWAY PAVEMENT REMOVAL		
LOCATION STATION	LT/RT	AREA
		SQ YD
STA. 179+96.90	RT	15.9
STA. 181+31.20	LT	332.14
STA. 184+03.30	LT	318.4
STA. 194+04.00 & 194+40.00	LT	342.7
TOTAL		1009.14

CURB CUT		
LOCATION	LT/RT	LENGTH
		FOOT
STA. 198+96.00	LT	15.3
STA. 199+55.00	LT	14
STA. 202+67.00	LT	10.5
STA. 203+11.00	LT	13
STA. 208+77.00	LT	16
TOTAL		68.8

SCHEDULE OF QUANTITIES

 ALLEN ROAD
 F.A.U. 6584 (SBI 174) SECTION 105R-1
 PEORIA COUNTY