


DESIGNED AMPH/RB	 RANDOLPH & ASSOCIATES, INC. 901 N. FLOWER PARKWAY, PEORIA, IL 61614-2124 TEL: 309-693-0014 FAX: 309-693-0025 • 1-800-891-1021 811 E. P. O. BOX 1000, PEORIA, IL 61601-1000 CONSULTING ENGINEERS • LAND SURVEYORS	FILE NUMBER 136.115	F.A.U. RTE. 6584	SECTION 105R-1	COUNTY PEORIA	TOTAL SHEETS 115	SHEET NO. 17
CHECKED RB		DATE February 2004	STA.	TO STA.			
DRAWN AMP							
CHECKED RD							

LOCATION	STRUCTURE NUMBER	RIM ELEVATION	INVERT ELEVATION	INLET TY A, TY 8 CRATE	INLET, TYPE G-1, SPECIAL	INLET TYPE B, TYPE 1 FRAME, CLOSED LID	INLET MANHOLE, TYPE G-1, 6' DIA., SPECIAL	INLET MANHOLE, TYPE G-1, 5' DIA., SPECIAL	INLET MANHOLE, TYPE G-1, SPECIAL, 4' DIA.	MANHOLE TY A, 4' DIA. TY 1 FRAME, CLOSED LID	MANHOLE TY A, 4' DIA. TY 8 GRATE
STA. 178+63.00, 32.00' RT	1	796.84	793.40		1						
STA. 178+63.00, 40.00' RT	2	797.43	793.06							1	
STA. 180+98.84, 40.10' RT	3	798.83	794.25							1	
STA. 180+98.84, 32.00' RT	4	798.35	794.48		1						
STA. 182+82.00, 31.00' RT	5	799.25	795.96		1						
STA. 180+69.50, 57.00' LT	6	797.80	795.04	1							
STA. 180+53.00, 32.00' LT	7	797.61	794.70		1						
STA. 182+70.00, 57.30' LT	8A	802.36	796.32			1					
STA. 182+70.00, 31.00' LT	8	799.19	796.10		1						
STA. 184+39.80, 31.00' LT	9	800.60	797.00		1						
STA. 184+54.00, 58.00' LT	10	799.00	797.25	1							
STA. 184+91.00, 31.00' RT	11	800.43	791.70				1				
STA. 184+91.00, 31.00' LT	12	800.90	793.33		1						
STA. 184+80.00, 66.00' LT	13	799.30	793.56	1							
STA. 187+10.90, 31.00' LT	14	801.42	794.15					1			
STA. 188+16.75, 31.00' LT	14A	802.54	796.90		1						
STA. 187+10.90, 31.00' RT	15	801.42	792.70				1				
STA. 187+10.90, 54.50' RT	15A	798.28	795.28	1							
STA. 189+23.30, 31.00' RT	16	802.63	794.90						1		
STA. 189+50.00, 50.60' RT	16A	799.73	795.15								1
STA. 22+14.80, 13.20' LT	17	801.58	797.20		1						
STA. 22+14.80, 12.60' RT	18	801.48	797.54		1						
STA. 189+15.60, 31.00' LT	19	802.57	799.13		1						
STA. 190+95.00, 31.00' LT	20	803.50	796.66				1				
STA. 192+20.75, 46.00' LT	21	804.83	800.00							1	
STA. 192+91.00, 31.00' LT	22	804.41	800.96		1						
STA. 190+95.00, 31.00' RT	24	803.50	795.80				1				
STA. 193+00.00, 31.00' RT	25	804.44	800.15		1						
STA. 194+93.68, 31.00' RT	26	805.47	801.10		1						
STA. 195+06.67, 31.00' LT	27	805.55	801.50		1						
TOTAL				4	15	1	2	3	1	3	1

LOCATION STATION	OFFSET	LT/RT	EACH
STA. 184+91.00	59.5	RT	1
TOTAL			1

LOCATION STATION	OFFSET	LT/RT	AREA
			SQ YD
STA. 184+91.00	64.00	RT	27.77
TOTAL			27.77

LOCATION STATION	OFFSET	LT/RT	LENGTH
			FOOT
STA. 184+91.00	31	RT	18.1
TOTAL			18.1

LOCATION STATION	OFFSET	LT/RT	AREA
			SQ YD
STA. 184+91.00	64.00	RT	27.77
TOTAL			27.77

LOCATION STATION TO STATION	LT/RT	AREA SQ YD
STA. 184+92.00 TO STA. 187+25.50	RT	271
TOTAL		271

SCHEDULE OF QUANTITIES

 ALLEN ROAD
 F.A.U. 6584 (SBI 174) SECTION 105R-1
 PEORIA COUNTY