

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
693	15 RS-2, 118 RS-4	TAZEWELL	28	14

CONTRACT NO. 68375

RAISED REFLECTIVE PAVEMENT MARKERS			
LOCATION	CRYSTAL ONE WAY	AMBER ONE WAY	AMBER TWO WAY
	EACH	EACH	EACH
STA. 68+82 TO 81+12	38	9	17
STA. 81+12 TO 87+50	16		32
STA. 87+50 TO 93+00	15		24
STA. 93+00 TO 98+50	14		24
STA. 98+50 TO 104+00	14		28
STA. 104+00 TO 67+50 (AH)	16		30
STA. 67+50 TO 74+00	27	28	
STA. 74+00 TO 80+00	8	20	
STA. 80+00 TO 86+00	10	28	
STA. 86+00 TO 87+75	4	4	
TOTAL	162	89	155
GRAND TOTAL	406		

BITUMINOUS SURFACE REMOVAL BUTT JOINT			
LOCATION	WIDTH	LENGTH	AREA
	FOOT	FOOT	SQ YD
STA. 68+82 TO 68+92	52	10	57.8
STA. 87+65 TO 87+75	68	10	75.6
TURN LANES			
LT. STA. 75+25 (PARKWAY)	14	10	15.6
RT. STA. 70+40 (VALLE VISTA)	16	10	17.8
LT. STA. 71+70 (VALLE VISTA)	16	10	17.8
RT. STA. 72+10 (VALLE VISTA)	10	10	11.1
LT. STA. 84+00 (OLT)	14	10	15.6
TOTAL			211

CLASS D PATCHES, TYPE II 14"	
LOCATION	SQ YD
EAST BOUND LANES	
STA. 68+82 TO 87+75	472
WEST BOUND LANES	
STA. 68+82 TO 87+75	357
MEDIAN	159
TOTAL	988
ADD 15% FOR WINTER BREAKUP	148
GRAND TOTAL	1136

TEMPORARY RAMP	
LOCATION	SQ YD
STA. 68+82 TO 68+87	28.9
STA. 87+70 TO 87+75	26.7
SIDE ROADS	112
TOTAL	168

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES