F.A.P. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(1198-3)I	TAZEWELL	34	3
STA.		TO STA.		

EXISTING CONDITIONS:

CONTRACT NO. 68415

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: X080-2A FED 80% STATE 20%	SFTY-3N				
20200500	EARTH EXCAVATION (WIDENING)	CU YD	50	50					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35	35					
35600400	BITUMINOUS CONCRETE BASE COURSE WIDENING, 9"	SQ YD	196	196					
40600300	AGGREGATE (PRIME COAT)	TON	1	1					
40600980	BITUMINOUS CONCRETE REMOVAL - BUTT JOINT	SQ YD	160	160					
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	164	164					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35					
44000100	PAVEMENT REMOVAL	SQ YD	92	92					
44000700	APPROACH SLAB REMOVAL	SQ YD	107	107					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3	3					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1					
50102400	CONCRETE REMOVAL	CU YD	2.4	2.4					
50300225	CONCRETE STRUCTURES	CU YD	3.4	3.4					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH=/<5")	SQ FT	45.1	45.1					
X0325294	PREFORMED JOINT STRIP SEAL	FOOT	33	33					
X0324744	REMOVAL OF EXISTING PRECAST UNITS	SQ FT	299	299					
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299	299					
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	2,066	2,066					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	450	450					
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	207	207					
51500100	NAME PLATES	EACH	1	1					
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	230	230					
58300100	PC MORTAR FAIRING COURSE	FOOT	626	626					
* 63000000	STEEL PLATE BRIDGE GUARD RAIL, TYPE A	FOOT	100	100					
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4					
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	125	125					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1					
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	144	144					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,107	3,107					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,132	1,132					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	329	329					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	329	329					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,689	1,689					
* 78100100	RAISED REFECTIVE PAVEMENT MARKERS	EACH	10	10					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4					
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	4	4					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	473	473					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: X080-2A FED 80% STATE 20%	SFTY-3N FED 80% STATE 20%				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10					
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	53	53					
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	21	21					
* X7200200	WIDE LOAD SIGNING	L SUM	1	1					
Z0002600	BAR SPLICERS	EACH	8	8					
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2		2				
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2		2				

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: X080-2A FED 80% STATE 20%					
20300100	CHANNEL EXCAVATION	CU YD	416		416				
25000300	SEEDING, CLASS 3	ACRES	0.03		0.03				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3		3				
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	3		3				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3		3				
25100630	EROSION CONTROL BLANKET	SQ YD	138		138				
28100109	STONE RIPRAP, CLASS A5	TON	129		129				
28200200	FILTER FABRIC	SQ YD	712		712				
28400100	GABIONS	CU YD	167		167				
28401000	SLOPE MATTRESS	SQ YD	307		307				
31101900	SUB-BASE GRANULAR MATERIAL TYPE C	TON	171		171				
63300205	REMOVE AND REINSTALL EXIST. STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50		50				
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1		1				
X0322587	CONSTRUCTION ACCESS	EACH	1		1				
X0323655	GABION ANCHOR STAKES	EACH	56		56				

*SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE. 693
SECTION (1198-3)I
TAZEWELL COUNTY

SCALE: NONE — DRAWN BY: KBF

DATE: 03/24/2006 — CHECKED BY: AJE