

70119

**SUMMARY OF QUANTITIES**

CONTRACT NO. 70119

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	VERMILION	30	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\*RX,4BZ-1RS-1&amp;147R-1RS

## LOCATION OF WORK:

FAP 332 (US136/IL1)  
STA. 183+00 TO 251+25

URBAN

80% FEDERAL  
20% STATE

## CONSTRUCTION TYPE CODE:

1000  
TOTAL  
QUANTITY

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,066.0
40600300	AGGREGATE (PRIME COAT)	TON	182.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	65.0
44201777	CLASS D PATCH, TYPE II, 11 INCH	SQ YD	26.7
44201781	CLASS D PATCH, TYPE III, 11 INCH	SQ YD	16.0
44201798	CLASS D PATCH, TYPE I, 13 INCH	SQ YD	8.0
44201803	CLASS D PATCH, TYPE II, 13 INCH	SQ YD	10.7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,460.0
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	1,357.0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	17,423.0
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	1,219.0
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	375.0