

70119

**SUMMARY OF QUANTITIES**

CONTRACT NO. 70119				
F.A.P. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	VERMILION	30	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*RX,4BZ-1RS-1&147R-1RS				

LOCATION OF WORK:

FAP 332 (US136/IL1)  
STA. 183+00 TO 251+25

URBAN  
80% FEDERAL  
20% STATE

CONSTRUCTION TYPE CODE:

1000  
TOTAL  
QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,802.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,357.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,423.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,219.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	375.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	563.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	563.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2,561.0
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	3,808.0
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	2,538.0
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	45,329.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	14.0

\* SPECIALTY ITEMS

PLOT DATE = 3/24/2005  
PLOT SCALE = 43.225' / IN.  
USER NAME = cbrndt-s