

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CONTRACT NO. 72232				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* FAP 325 & FAP 604 ** 14R; 115RS-2; 116RS-4; 101RS-2				

LOCATION OF WORK				ROADWAY IMPROVEMENT	LANDSCAPING IMPROVEMENT	ROADWAY IMPROVEMENT	ROADWAY IMPROVEMENT	BITUMINOUS ROADWAY	DRAINAGE IMPROVEMENT	PARKING LANES	ROADWAY IMPROVEMENT
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	100% CITY WARREN ST & IL 159 PARKING AREAS	100% CITY ALTON ST	50% STATE 50% CITY IL 159	80% FEDERAL 20% STATE IL 159
				IL 16 / IL 159	IL 16 / IL 159	IL 159	IL 159	PART C	PART C	PART C	PART D
				PART A	PART A	PART B	PART C	PART C	PART C	PART C	PART D
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000	Y003	1000	1000	Y025	Y007	Y025	1000
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	278	278							
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	358	358							
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	94	94							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1309	103		755	37				414
70400100	TEMPORARY CONCRETE BARRIER	FOOT	187.5				187.5				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	175				175				
* 72000100	SIGN PANEL - TYPE 1	SO FT	190.5	190.5							
* 72000200	SIGN PANEL - TYPE 2	SO FT	85.4	85.4							
* 72000300	SIGN PANEL - TYPE 3	SO FT	28.7	28.7							
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	450	450							
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	29,872	9,324		2,450	12,829				5,269
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,280				1,280				
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	82,153	2,859		52,425					26,869
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	109.20	109.20							
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1,505			306	737				462
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1,503	595			908				
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	272	228			44				
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	140	37			103				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	614	72		301	60				181
78300100	PAVEMENT MARKING REMOVAL	SO FT	785	785							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	614	72		301	60				181
* A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	13		13						
* A2003816	TREE, FRAXINUS PENNSYLVANICA (GREEN ASH) 2" CALIPER, BALLED AND BURLAPPED	EACH	12		12						
* A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6		6						
X0323665	RIPRAP SLURRY	SO YD	216			216					
X0324118	GRANULAR CULVERT BACKFILL	CU YD	120				120				
X0545000	BOX CULVERT REMOVAL	FOOT	71	71							
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SO YD	976				976				
X3550600	BITUMINOUS BASE COURSE SUPERPAVE 9"	SO YD	3,387	3,387							
X3550800	BITUMINOUS BASE COURSE SUPERPAVE 11"	SO YD	547	440			107				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 325 (IL 16) & FAP 604 (IL 159)
SECTION 14R; 115RS-2; 116RS-4; 101RS-2
MACOUPIN COUNTY
SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE

DDN-SPEC
DATE-TIME
*REF 01