

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 325 & FAP 604
** 14R; 115RS-2; 116RS-4; 101RS-2

LOCATION OF WORK				ROADWAY IMPROVEMENT	LANDSCAPING IMPROVEMENT	ROADWAY IMPROVEMENT	ROADWAY IMPROVEMENT	BITUMINOUS ROADWAY	DRAINAGE IMPROVEMENT	PARKING LANES	ROADWAY IMPROVEMENT
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	100% CITY WARREN ST & IL 159 PARKING AREAS	100% CITY ALTON ST	50% STATE 50% CITY IL 159	80% FEDERAL 20% STATE IL 159
				IL 16 / IL 159	IL 16 / IL 159	IL 159	IL 159	PART C	PART C	PART C	PART D
				PART A	PART A	PART B	PART C	PART C	PART C	PART C	PART D
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	Y003	I000	I000	Y025	Y007	Y025	I000
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SO YD	452	374			78				
X3560150	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 11 INCH	SO YD	782	69			713				
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	11,832	1,222		5,796	1,293	249		80	3,192
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	929	929							
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	5,916	611		2,898	646.5	124.5		40	1,596
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	2,373	100		445	1,319				509
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SO YD	10,931			891	4,396	3,773		1,871	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	1,562	94		150	978				340
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	23.7	4.1			19.6				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2				2				
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1				1				
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1				1				
Z0062450	SAWING PAVEMENT (FULL DEPTH)	FOOT	779	779							
X0325365	RESTRICTED DEPTH INLET TYPE B, TYPE 8 GRATE	EACH	3				3				

© SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 325 (IL 16) & FAP 604 (IL 159)
SECTION 14R; 115RS-2; 116RS-4; 101RS-2
MACOUPIN COUNTY
SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____

DGN-SPEC
DATE-TIME
*REF01