

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	27
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 325 (IL 16) & FAP 604 (IL 159)
 ** 14R; 115RS-2; 116RS-4; 101RS-2

CULVERT REMOVAL

LOCATION	PIPE / BOX SIZE	PIPE MATERIAL	PIPE CULV REM (FOOT)	PIPE CULV REM SPL (FOOT)	BOX CULV REM (FOOT)	CONC HDWL REM (EACH)	REMOVING INLETS (EACH)	CLSM (CU YD)
PART A								
IL 16 (E-W PORTION)								
LT STA 1134+80.12	24"	CMP	31.8					
LT STA 1137+85.00	2' x 1.5'	CONC			46.1	2		
STA 1139+00.00	2' x 1.5'	CONC			25.2	2		
IL 159 (N-S PORTION)								
RT STA 110+27.55	18"	CONC	30.7			2		
STA 109+89.00	2' x 1.5'	CONC				2		4.1
PART B								
RT STA 1221+67.08	24"	CMP	37.6					
RT STA 181+18.84	12"	CLAY	17.5			2		
LT STA 187+95.88	12"	CMP	21.1					
PART C								
IL 159								
LT STA 188+56.33	15"	CMP	50.5					
RT STA 188+81.56	12"	CLAY	18.7			2		
LT STA 189+63.92	12"	CONC	36.1			2		
LT STA 190+44.50	12"	CONC	41.2			2		
LT STA 192+43.97	12"	CONC	29.6			2		
LT STA 192+96.35	12"	CONC	21.5			1		
LT STA 193+53.40	12"	CONC	42.0					
LT STA 194+35.05	12"	CONC	37.2					
RT STA 194+79.07	12"	CLAY	47.0			2		
LT STA 194+87.06	12"	CONC	46.7			2		
RT STA 196+08.73	12"	CLAY	31.6			2		
RT STA 196+91.16	15"	CMP	44.0					
LT STA 197+16.47	12"	CMP	25.4					
LT STA 198+22.14	12"	CLAY	47.3					
RT STA 198+22.14	12"	CMP	46.3			2		
RT STA 199+36.59	12"	CONC	19.3					
RT STA 6+35.22	18"	CLAY	54.3			2		
RT STA 6+96.99	18"	CONC	33.7			1		
RT STA 7+48.88	18"	CONC	66.5			2		
RT STA 7+92.00	INLET						1	
RT STA 8+07.36	15"	CLAY	71.9			2		
RT STA 9+66.82	18"	CLAY	51.0			2		
RT STA 10+81.24	18"	CONC	50.4					
LT STA 11+17.29	18"	CLAY	18.5			2		
LT STA 11+49.00	18"	CLAY	18.9			2		
RT STA 11+36.20	18"	CONC	29.7					
RT STA 11+76.90	18"	CONC	26.8			2		
LT STA 12+03.92	18"	CLAY	18.8			2		
RT STA 12+09.88	18"	CLAY	18.5			2		
LT STA 12+48.12	18"	CLAY	18.6			2		
RT STA 12+78.00	24"	CONC	29.3					
RT STA 13+15.34	24"	CONC	21.8					
LT STA 13+25.01	18"	CLAY	18.6			2		
RT STA 13+90.18	24"	CLAY	18.5			2		
LT STA 14+95.00	24"	CLAY	24.2			2		
RT STA 15+32.04	24"	CLAY	26.2			2		
RT STA 15+87.14	24"	CMP	24.0					
LT STA 16+48.71	24"	CLAY	18.4			2		
RT STA 16+51.82	24"	CLAY	18.6					
RT STA 16+94.44	24"	CLAY	36.6					
LT STA 17+98.60	24"	CLAY	43.8			2		
RT STA 17+98.60	24"	CLAY	41.6			1		
LT STA 19+45.50	24"	CONC	39.7					
LT STA 19+89.85	24"	CLAY	40.5					
LT STA 20+44.24	24"	CLAY	18.4			2		
LT STA 21+03.89	24"	CLAY	18.4			2		
RT STA 22+02.26	24"	CONC	41.8					
LT STA 22+37.76	24"	CLAY	18.4			2		
RT STA 22+72.09	24"	CONC	41.8					
STA 23+75.00	5' x 2'	CONC				2		14.7
RT STA 24+18.40	36"	CONC	22.1			2		
LT STA 24+19.00	18"	CMP	32.0					
LT STA 24+68.75	15"	CMP	47.2					
LT STA 25+92.04	15"	CMP	53.0					
RT STA 25+92.52	48"	CONC	46.6					
STA 27+75.00	2' x 1.5'	CONC				2		4.9
RT STA 28+44.59	15"	CONC	37.3					
LT STA 28+84.03	12"	CONC	37.8					
ALTON								
LT STA 7+95.13	24"	STEEL	95.1					
LT STA 8+15.00	15"	CONC		10.0				
LT STA 8+62.05	36"	CMP	31.2					
RT STA 8+97.29	12"	CONC	23.3					
STA 10+32.44	15"	CONC	32.6					
RT STA 11+75.00	12"	CONC		60.0				
LT STA 11+16.86	12"	CONC	31.7					
PART D								
STA 33+90.20	12"	CLAY	33.2			2		
			2264.4	70.0	71.3	75	1	23.7

PAVEMENT REMOVAL

LOCATION	AREA (SQ YD)
PART A	
EAST LEG	
STA 1130+91.37 TO STA 1136+05.42	392.02
TEMP WIDENING	
STA 1133+10.42 TO STA 8+89.75	316.61
NORTH LEG	
STA 7+15.70 TO STA 13+59.03	1,563.79
TEMP WIDENING	
STA 111+95.83 TO STA 112+96.17	190.18
SOUTH LEG	
STA 1137+00.00 TO STA 1143+13.70	1,501.21
PART C	
IL 159	
STA 25+15.00 TO STA 25+45.00	93.33
ALTON ST	
STA 8+32.00 TO STA 9+87.40	631.72
STA 10+13.65 TO STA 10+79.00	170.65
	4,859.51

SAWING PAVEMENT (FULL DEPTH)

LOCATION	LENGTH (FOOT)
PART A	
EAST LEG	
STA 1130+91.37 TO STA 1137+00.00	608.63
STA 1137+00.00	29.80
NORTH LEG	
STA 13+08.00 TO STA 13+59.00	51.70
STA 13+08.00	9.20
SOUTH LEG	
STA 1142+44.70 TO STA 1143+09.20	68.20
STA 1137+00.00 TO STA 1143+13.70	11.60
	779.13

CURB & GUTTER

LOCATION	REMOVAL (FOOT)	CCC&G TY B-6, 18 (FOOT)
PART C		
MEDIAN SOUTH OF WARREN	179.0	99.0
	179.0	99.0

SIDEWALK

LOCATION	REMOVAL (SQ YD)	PCC SW 4" (SQ YD)
PART C		
STA 195+58.00 TO STA 195+62.00	25.77	25.77
STA 6+61.00 TO STA 6+65.00	29.41	29.41
STA 9+36.00 TO STA 9+40.00	37.27	37.27
STA 18+21.00 TO STA 18+25.00	32.76	32.76
STA 23+06.00 TO STA 24+49.00	432.66	
STA 23+06.00 TO STA 24+30.00		420.11
STA 27+04.00 TO STA 27+29.00	65.52	
	623.39	545.32

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 325 (IL 16) & FAP 604 (IL 159)
 14R; 115RS-2; 116RS-4; 101RS-2
 MACOUPIN COUNTY
 SCALE: VERT. DATE
 HORIZ. DRAWN BY
 CHECKED BY

PLOT DATE = #DATES
 FILE NAME = #FILES
 PLOT SCALE = #SCALE#
 USER NAME = #USER#