

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	29
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 325 (IL 16) & FAP 604 (IL 159)
 ** 14R; 115RS-2; 116RS-4; 101RS-2

SUB-BASE GRANULAR MATERIAL, TYPE A 8"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART A			
IL 16 (E-W PORTION)			
RT STA 1128+51.13 TO STA 1137+00.00	848.87	2.75 & VAR	925.32
STA 1137+00.00 TO STA 1138+96.04	196.04	28	609.91
STA 1138+96.04 TO STA 1140+71.85	175.81	28 & VAR	854.28
IL 159 (N-S PORTION)			
LT STA 101+51.78 TO STA 105+69.75	417.97	2.75 & VAR	215.74
RT STA 103+00.00 TO STA 107+00.00	400.00	2.75 & VAR	126.38
LT STA 106+50.00 TO STA 108+98.26	248.26	10.64 TO 26.65	415.23
LT STA 108+98.26 TO STA 110+56.04	157.78	26.65 TO 26.27	464.52
LT STA 110+56.04 TO STA 113+48.31	292.27	26.27 TO 0	761.78
LT STA 113+79.78 TO STA 118+12.42	432.64	2.75 & VAR	298.91
PART C			
IL 159			
STA 0+01.26 TO STA 0+78.45	77.19	MEDIAN	77.72
			4,749.79

SUB-BASE GRANULAR MATERIAL, TYPE B

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	DEPTH (INCH)	TONS
PART C					
ALTON ST					
STA 8+32.00 TO STA 9+87.40	155.40	VAR	705.48	4.00	160.69
STA 10+13.65 TO STA 10+79.00	65.35	VAR	346.67	4.00	78.96
					239.65

BITUMINOUS BASE COURSE SUPERPAVE 8"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART C			
ALTON ST			
STA 8+32.00 TO STA 9+87.40	155.40	VAR	652.95
STA 10+13.65 TO STA 10+79.00	65.35	VAR	323.16
			976.11

BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART A			
IL 16 (E-W PORTION)			
RT STA 1128+51.13 TO STA 1131+99.25	348.12	1 TO 6	92.77
IL 159 (N-S PORTION)			
LT STA 101+51.78 TO STA 105+69.75	417.97	1 & VAR	134.50
RT STA 103+00.00 TO STA 107+00.00	400.00	1 & VAR	48.61
LT STA 113+79.78 TO STA 114+19.35	39.57	1 TO 6	15.23
LT STA 115+59.14 TO STA 118+12.42	253.28	6 TO 1	82.95
PART C			
STA 0+01.26 TO STA 0+78.45			
		MEDIAN	77.72
			451.78

BITUMINOUS BASE COURSE SUPERPAVE 9"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART A			
IL 16 (E-W PORTION)			
RT STA 1131+99.25 TO STA 1135+50.50	351.25	6 TO 16.04	425.73
STA 1137+00.00 TO STA 1138+96.04	196.04	24.5	533.68
STA 1138+96.04 TO STA 1140+71.85	175.81	24.5 & VAR	804.40
IL 159 (N-S PORTION)			
LT STA 106+50.00 TO STA 108+98.26	248.26	8.89 TO 24.86	366.81
LT STA 108+98.26 TO STA 110+56.04	157.78	24.86 TO 24.52	433.32
LT STA 110+56.04 TO STA 112+08.68	152.64	24.52	416.22
LT STA 112+08.68 TO STA 113+32.00	123.32	24.52 TO 6	290.50
LT STA 114+19.35 TO STA 115+59.14	139.79	6 & VAR	116.60
			3,387.26

BITUMINOUS BASE COURSE SUPERPAVE 11"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART A			
IL 16 (E-W PORTION)			
LT STA 1134+57.81 TO STA 1136+82.76	224.95	6 & VAR	257.47
IL 159 (N-S PORTION)			
LT STA 112+08.68 TO STA 113+32.00	123.32	6 & VAR	182.64
PART C			
IL 159			
STA 25+15.00 TO STA 25+45.00	30.00	32	106.67
			546.78

BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 11 INCH

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
PART A			
IL 16 (E-W PORTION)			
LT STA 1133+09.96 TO STA 1134+57.81	147.85	1 TO 6	36.44
LT STA 1136+82.76 TO STA 1137+69.38	86.62	6 TO 1	22.70
IL 159 (N-S PORTION)			
LT STA 111+95.83 TO STA 112+13.15	17.32	0 TO 6	5.29
LT STA 113+32.00 TO STA 113+48.31	16.31	6 TO 0	4.60
PART C			
LT STA 188+25.00 TO STA 200+00.00	1,175.00	2.5	326.39
RT STA 188+25.00 TO STA 200+00.00	1,175.00	2.5	326.39
LT STA 24+89.00 TO STA 25+64.50	75.50	4	33.56
RT STA 24+82.50 TO STA 25+15.00	32.50	4	14.44
RT STA 25+45.00 TO STA 25+73.00	28.00	4	12.44
			782.25

PLOT DATE : #DATES
 FILE NAME : #FILE#
 PLOT SCALE : #SCALE#
 USER NAME : #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 325 (IL 16) & FAP 604 (IL 159)
 14R; 115RS-2; 116RS-4; 101RS-2
 MACOUPIN COUNTY
 SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE