

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	31
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* FAP 325 (IL 16) & FAP 604 (IL 159)  
 \*\* 14R; 115RS-2; 116RS-4; 101RS-2

BITUMINOUS MATERIAL (PRIME COAT)

LOCATION	PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH (FOOT)	QUANTITY (TONS)
<b>PART A</b>			
IL 16 (E-W PORTION)			
STA 1127+21.20 TO STA 1138+96.04	24		1.19
STA 1138+96.04 TO STA 1140+72.23	VAR		0.30
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 118+12.42	24		0.10
STA 118+12.42 TO STA 114+92.45	24 TO 32		0.38
STA 114+92.45 TO STA 112+52.12	32 TO 48		0.41
STA 112+52.12 TO STA 108+96.94	48		0.72
STA 108+96.94 TO STA 108+03.34	48 TO 36		0.17
STA 108+03.34 TO STA 101+51.77	36 TO 26		0.85
STA 101+51.77 TO STA 101+26.77	26		0.03
<b>PART B</b>			
STA 1149+43.64 AH TO STA 1154+95.82 BK	26		0.61
STA 1154+99.92 AH TO STA 1209+05.36	26		5.93
STA 1209+05.36 TO STA 1211+70.89	26	2.3 TO 13.5	0.38
STA 1211+70.89 TO STA 1213+90.00	26	13.5	0.37
STA 1213+90.00 TO STA 1214+40.00	26		0.05
STA 1214+40.00 TO STA 1216+50.35	26	13.5	0.35
STA 1216+50.35 TO STA 1219+22.83	26	13.5 TO 2.3	0.39
STA 1219+22.83 TO STA 1280+02.26 BK	26		6.67
STA 1280+11.77 AH TO STA 1293+48.10 BK	26		1.47
STA 1293+53.91 AH TO STA 1304+24.50 BK	26		1.18
STA 104+01.66 AH TO STA 188+25.00	26		9.25
<b>PART C</b>			
STA 188+25.00 TO STA 199+97.00	26		1.29
PARKING - FAYETTE (NW)	VAR		0.06
PARKING - FAYETTE (NE)	VAR		0.14
STA 199+97.00 TO STA 201+77.68	VAR		0.36
STA 201+77.68 TO STA 204+58.12	74		0.88
STA 204+58.12 TO STA 0+03.30	VAR		0.35
W WARREN ST	VAR		0.69
E WARREN ST	VAR		0.68
PARKING - WARREN (SW)	VAR		0.23
PARKING - WARREN (SE)	VAR		0.31
PARKING - NE PARK ST	VAR		0.12
STA 0+03.30 TO STA 0+49.00	36 TO 34		0.07
STA 0+49.00 TO STA 0+84.00	40.2 TO 31.3		0.05
STA 0+84.00 TO STA 1+61.62	31.3 TO 24		0.09
STA 1+61.62 TO STA 30+00.00	24		2.88
ALTON ST			0.37
<b>PART D</b>			
STA 30+00.00 TO STA 30+61.01 BK	24		0.06
STA 31+09.65 AH TO STA 51+64.30 BK	24		2.08
STA 53+55.92 AH TO STA 91+74.78 BK	24		3.87
STA 91+75.20 AH TO STA 106+20.58 BK	24		1.46
STA 106+24.40 AH TO STA 124+31.79 BK	24		1.83
STA 124+36.47 AH TO STA 165+49.56 BK	24		4.17
STA 165+56.00 AH TO STA 175+07.05	24		0.96
			53.80

AGGREGATE (PRIME COAT)

LOCATION	PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH (FOOT)	QUANTITY (TONS)
<b>PART A</b>			
IL 16 (E-W PORTION)			
STA 1127+21.20 TO STA 1138+96.04	24		6.27
STA 1138+96.04 TO STA 1140+72.23	VAR		1.60
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 118+12.42	24		0.53
STA 118+12.42 TO STA 114+92.45	24 TO 32		1.99
STA 114+92.45 TO STA 112+52.12	32 TO 48		2.14
STA 112+52.12 TO STA 108+96.94	48		3.79
STA 108+96.94 TO STA 108+03.34	48 TO 36		0.87
STA 108+03.34 TO STA 101+51.77	36 TO 26		4.49
STA 101+51.77 TO STA 101+26.77	26		0.14
<b>PART B</b>			
STA 1149+43.64 AH TO STA 1154+95.82 BK	26		3.19
STA 1154+99.92 AH TO STA 1209+05.36	26		31.23
STA 1209+05.36 TO STA 1211+70.89	26	2.3 TO 13.5	2.00
STA 1211+70.89 TO STA 1213+90.00	26	13.5	1.92
STA 1213+90.00 TO STA 1214+40.00	26		0.29
STA 1214+40.00 TO STA 1216+50.35	26	13.5	1.85
STA 1216+50.35 TO STA 1219+22.83	26	13.5 TO 2.3	2.05
STA 1219+22.83 TO STA 1280+02.26 BK	26		35.13
STA 1280+11.77 AH TO STA 1293+48.10 BK	26		7.72
STA 1293+53.91 AH TO STA 1304+24.50 BK	26		6.19
STA 104+01.66 AH TO STA 188+25.00	26		48.67
<b>PART C</b>			
STA 188+25.00 TO STA 199+97.00	26		6.77
PARKING - FAYETTE (NW)	VAR		0.30
PARKING - FAYETTE (NE)	VAR		0.73
STA 199+97.00 TO STA 201+77.68	VAR		1.92
STA 201+77.68 TO STA 204+58.12	74		4.61
STA 204+58.12 TO STA 0+03.30	VAR		1.84
W WARREN ST	VAR		3.63
E WARREN ST	VAR		3.58
PARKING - WARREN (SW)	VAR		1.19
PARKING - WARREN (SE)	VAR		1.65
PARKING - NE PARK ST	VAR		0.63
STA 0+03.30 TO STA 0+49.00	36 TO 34		0.36
STA 0+49.00 TO STA 0+84.00	40.2 TO 31.3		0.28
STA 0+84.00 TO STA 1+61.62	31.3 TO 24		0.48
STA 1+61.62 TO STA 30+00.00	24		15.14
ALTON ST			1.95
<b>PART D</b>			
STA 30+00.00 TO STA 30+61.01 BK	24		0.33
STA 31+09.65 AH TO STA 51+64.30 BK	24		10.96
STA 53+55.92 AH TO STA 91+74.78 BK	24		20.37
STA 91+75.20 AH TO STA 106+20.58 BK	24		7.71
STA 106+24.40 AH TO STA 124+31.79 BK	24		9.64
STA 124+36.47 AH TO STA 165+49.56 BK	24		21.94
STA 165+56.00 AH TO STA 175+07.05	24		5.07
			283.14

PLOT DATE : #DATES  
 FILE NAME : #FILEL#  
 PLOT SCALE : #SCALE#  
 USER NAME : #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP 325 (IL 16) & FAP 604 (IL 159)  
 14R; 115RS-2; 116RS-4; 101RS-2  
 MACOUPIN COUNTY  
 SCALE: VERT. \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 HORIZ. \_\_\_\_\_ CHECKED BY \_\_\_\_\_  
 DATE \_\_\_\_\_