

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	35
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 325 (IL 16) & FAP 604 (IL 159)
 ** 14R; 115RS-2; 116RS-4; 101RS-2

PAVEMENT MARKING REMOVAL

LOCATION	# OF LINES	LENGTH (FOOT)	WIDTH (INCH)	AREA (SQ FT)
PART A				
PRIOR TO STAGE 2				
WHITE EDGE LINES				
IL 16 (E-W PORTION)				
STA 1133+65.52 TO STA 1136+05.42	1	239.90	5	99.96
STA 7+15.70 TO STA 8+89.75	1	174.10	5	72.54
YELLOW CENTERLINE				
IL 16 (E-W PORTION)				
STA 1133+65.52 TO STA 1136+05.42	2	479.80	5	199.92
STA 7+15.70 TO STA 8+89.75	2	348.10	5	145.04
AFTER STAGE 2				
WHITE EDGE LINES				
IL 16 (E-W PORTION)				
STA 1133+65.52 TO STA 1135+79.50	1	214.00	5	89.17
YELLOW CENTERLINE				
IL 16 (E-W PORTION)				
STA 1133+65.52 TO STA 1135+79.50	2	428.00	5	178.33
				784.96

TEMPORARY PAVEMENT MARKING - LINE 5"

LOCATION	LENGTH (FOOT)	# OF LINES	LENGTH (FOOT)
PART A			
PRIOR TO STAGE 2			
WHITE EDGE LINES			
IL 16 (E-W PORTION)			
STA 1133+65.52 TO STA 1136+05.42	248.50	2	497.00
LT STA 7+15.70 TO STA 8+89.75	174.00	1	174.00
RT STA 7+15.70 TO STA 8+19.96	104.20	1	104.20
IL 159 (N-S PORTION)			
LT STA 105+07.84 TO STA 106+50.11	142.30	1	142.30
LT STA 110+55.30 TO STA 111+97.13	212.50	1	212.50
YELLOW CENTERLINE			
IL 16 (E-W PORTION)			
STA 1133+65.52 TO STA 1136+05.42	248.50	2	497.00
STA 7+15.70 TO STA 12+64.56	554.25	2	1,108.50
AFTER STAGE 2			
WHITE EDGE LINES			
IL 16 (E-W PORTION)			
STA 1127+21.20 TO STA 1138+96.00	1,174.80	2	2,349.60
STA 1138+96.00 TO STA 1140+15.80	119.80	1	119.80
NW RADIUS	208.00	1	208.00
SW RADIUS	201.50	1	201.50
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 110+56.00	856.12	2	1,712.20
STA 110+56.00 TO STA 110+25.60	30.40	1	30.40
STA 109+10.80 TO STA 107+90.50	120.30	1	120.30
STA 107+90.50 TO STA 101+51.80	638.70	2	1,277.40
STA 101+51.80 TO STA 101+26.77	25.03	2	50.10
YELLOW CENTERLINE			
IL 16 (E-W PORTION)			
STA 1127+21.20 TO STA 1140+52.80	1,331.60	0.25	332.90
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 118+12.11	100.01	0.25	25.00
STA 118+12.11 TO STA 111+52.10	660.01	4	2,640.00
STA 111+52.10 TO STA 110+37.10	115.00	2	230.00
STA 109+26.80 TO STA 108+11.80	115.00	2	230.00
STA 108+11.80 TO STA 101+51.80	660.00	4	2,640.00
STA 101+51.80 TO STA 101+26.77	25.03	0.25	6.30
			14,909.00

TEMPORARY PAVEMENT MARKING - LINE 6"

LOCATION	LENGTH (FOOT)	# OF LINES	LENGTH (FOOT)
PART A			
WHITE TURN LANES			
IL 159 (N-S PORTION)			
STA 114+92.50 TO STA 112+52.10	240.40	0.25	60.10
STA 112+52.10 TO STA 110+37.10	215.00	1	215.00
STA 113+32.10 TO STA 111+52.10	180.00	0.25	45.00
STA 111+52.10 TO STA 110+37.10	115.00	1	115.00
STA 109+26.80 TO STA 108+11.80	115.00	1	115.00
STA 108+11.80 TO STA 106+31.80	180.00	0.25	45.00
			595.10

TEMPORARY PAVEMENT MARKING - LINE 8"

LOCATION	LENGTH (FOOT)
PART A	
PRIOR TO STAGE 2	
WHITE - ISLAND	
IL 16 (E-W PORTION)	
STA 12+69.95 TO STA 13+96.01	278.30
	278.30

TEMPORARY PAVEMENT MARKING - LINE 12"

LOCATION	LENGTH (FOOT)	LENGTH (FOOT)
PART A		
PRIOR TO STAGE 2		
WHITE - ISLAND CHEVRONS		
IL 16 (E-W PORTION)		
STA 12+69.95 TO STA 13+96.01		129.80
PART A		
AFTER STAGE 2		
YELLOW MEDIAN CHEVRONS		
IL 159 (N-S PORTION)		
NORTH OF IL 16 (MEDIAN)	131.90	131.90
SOUTH OF IL 16 (MEDIAN)	96.30	96.30
		358.00

TEMPORARY PAVEMENT MARKING - LINE 24"

LOCATION	LENGTH (FOOT)
PART A	
WHITE STOP BARS	
IL 16 (E-W PORTION)	
STA 12+64.56	56.80
WHITE STOP BARS	
IL 16 (E-W PORTION)	
STA 1140+52.80	24.80
TR 800 (ACROSS FROM IL 16)	
STA 10+40.00	12.10
	93.70

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 325 (IL 16) & FAP 604 (IL 159)
 14R; 115RS-2; 116RS-4; 101RS-2
 MACOUPIN COUNTY
 SCALE: VERT. _____ DRAWN BY _____
 HORIZ. _____ CHECKED BY _____
 DATE _____