

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	37
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 325 (IL 16) & FAP 604 (IL 159)
 ** 14R; 115RS-2; 116RS-4; 101RS-2

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"

LOCATION	LENGTH (FOOT)	# OF LINES	LENGTH (FOOT)
PART A			
WHITE TURN LANES			
IL 159 (N-S PORTION)			
STA 114+92.50 TO STA 112+52.10	240.40	0.25	60.10
STA 112+52.10 TO STA 110+37.10	215.00	1	215.00
STA 113+32.10 TO STA 111+52.10	180.00	0.25	45.00
STA 111+52.10 TO STA 110+37.10	115.00	1	115.00
STA 109+26.80 TO STA 108+11.80	115.00	1	115.00
STA 108+11.80 TO STA 106+31.80	180.00	0.25	45.00
PART C			
WHITE CROSSWALKS			
FAYETTE			325.00
WARREN			582.80
			1,502.90

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS

LOCATION	QUANTITY (SQ FT)
PART A	
WHITE TURN ARROWS	
IL 159 (N-S PORTION)	
STA 108+09.00 LEFT	15.6
STA 109+09.00 LEFT	15.6
STA 110+55.00 LEFT	15.6
STA 110+56.00 RIGHT	15.6
STA 111+50.00 LEFT	15.6
STA 111+56.00 RIGHT	15.6
STA 112+56.00 RIGHT	15.6
	109.2

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"

LOCATION	LENGTH (FOOT)	LENGTH (FOOT)
PART A		
YELLOW CENTERLINE		
IL 159 (N-S PORTION)		
NORTH OF IL 16 (MEDIAN)	131.90	131.90
SOUTH OF IL 16 (MEDIAN)	96.30	96.30
PART C		
YELLOW DIAGONALS		
MEDIAN NORTH OF FAYETTE		23.80
MEDIAN SOUTH OF WARREN		20.40
		272.40

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	LENGTH (FOOT)	# OF LINES	LENGTH (FOOT)
PART A			
WHITE EDGE LINES			
IL 16 (E-W PORTION)			
NW RADIUS	208.00	1	208.00
SW RADIUS	201.50	1	201.50
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 110+56.00	856.12	2	1,712.20
STA 110+56.00 TO STA 110+25.60	30.40	1	30.40
STA 109+10.80 TO STA 107+90.50	120.30	1	120.30
STA 107+90.50 TO STA 101+51.80	638.70	2	1,277.40
YELLOW CENTERLINE			
IL 16 (E-W PORTION)			
STA 1140+15.80 TO STA 1140+52.80	37.00	0.25	9.30
IL 159 (N-S PORTION)			
STA 119+12.12 TO STA 118+12.11	100.01	0.25	25.00
STA 118+12.11 TO STA 111+52.10	660.01	4	2,640.00
STA 111+52.10 TO STA 110+37.10	115.00	2	230.00
STA 109+26.80 TO STA 108+11.80	115.00	2	230.00
STA 108+11.80 TO STA 101+51.80	660.00	4	2,640.00
PART B			
WHITE EDGE LINES			
STA 176+00.00 TO STA 188+25.00	1,225.00	2	2,450.00
PART C			
WHITE EDGE LINES			
STA 188+25.00 TO STA 200+00.00	1,175.00	2	2,350.00
STA 200+00.00 TO STA 201+30.00	145.00	2	290.00
STA 0+00.00 AH TO STA 30+00.00	3,000.00	2	6,000.00
YELLOW CENTERLINE			
STA 199+94.20 TO STA 201+26.00	145.00	2	290.00
STA 201+59.00 (AROUND STATLE)	71.00	1	71.00
STA 0+00.00 AH TO STA 0+99.00	110.00	2	220.00
STA 18+79.00 TO STA 24+14.00	535.00	1.25	668.80
STA 24+14.00 TO STA 30+00.00	586.00	2	1,172.00
WHITE PARKING			
FAYETTE TO WARREN	1,766.80		1,766.80
PART D			
WHITE EDGE LINES			
STA 30+00.00 TO STA 30+61.01 BK	61.01	2	122.00
STA 31+09.65 AH TO STA 51+64.30 BK	2,054.65	2	4,109.30
STA 53+55.92 AH TO STA 55+50.00	194.08	2	388.20
YELLOW CENTERLINE			
STA 30+00.00 TO STA 30+61.01 BK	61.01	2	122.00
STA 31+09.65 AH TO STA 31+42.00	32.35	2	64.70
STA 31+42.00 TO STA 35+12.00	370.00	1.25	462.50
			29,871.40

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"

LOCATION	LENGTH (FOOT)
PART A	
WHITE STOP BARS	
IL 16 (E-W PORTION)	
STA 1140+52.80	24.80
TR 800 (ACROSS FROM IL 16)	
STA 10+40.00	12.10
PART C	
IL 159	
STA 204+40.00	16.0
STA 0+20.00	14.8
E FAYETTE	18.6
W FAYETTE	14.2
E WARREN	20.0
W WARREN	19.6
	140.10

THERMOPLASTIC PAVEMENT MARKING - LINE 12"

LOCATION	LENGTH (FOOT)	LENGTH (FOOT)
PART C		
WHITE DIAGONALS LINES / PARKING		
WARREN TO FAYETTE	1,280.40	1,280.40
		1,280.40

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 325 (IL 16) & FAP 604 (IL 159)
 14R; 115RS-2; 116RS-4; 101RS-2
 MACOUPIN COUNTY
 SCALE: VERT. _____ DRAWN BY _____
 HORIZ. _____ CHECKED BY _____
 DATE _____

PLOT DATE : #DATES
 FILE NAME : #FILEL#
 PLOT SCALE : #SCALE#
 USER NAME : #USER#