

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	231	38

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* FAP 325 (IL 16) & FAP 604 (IL 159)
 ** 14R; 115RS-2; 116RS-4; 101RS-2

SIGNS

LOCATION	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	
PART A					
IL 16 (E-W PORTION)					
LT STA 1132+75.00	W3-1a (3636)	9.00		15	
RT STA 1132+75.00	W3-1a (3636)	9.00		15	
LT STA 1134+00.00	R2-1(3036)	7.50		15	
RT STA 1134+50.00	M2-1(2115)	2.19		15	
RT STA 1134+50.00	M1-1100(2424)	4.00			
RT STA 1136+50.00	M3-2(2412)	2.00		15	
RT STA 1136+50.00	M1-1100(2424)	4.00			
RT STA 1136+50.00	M5-1L(2115)	2.19			
RT STA 1136+50.00	M3-3(2412)	2.00			
RT STA 1136+50.00	M1-1100(2424)	4.00			
RT STA 1136+50.00	M5-1R(2115)	2.19			
LT STA 1137+00.00	SIGN001		16.25	30	
LT STA 1138+00.00	M3-4(2412)	2.00		15	
LT STA 1138+00.00	M1-1100(2424)	4.00			
RT STA 1138+00.00	SIGN002		16.25	30	
RT STA 1140+50.00	R1-1(3636)	9.00		15	
RT STA 1140+50.00	R1-1100(3018)	3.75			
LT STA 10+50.00	R1-1(3636)	9.00		15	
LT STA 10+50.00	R1-1100(3018)	3.75			
RT STA 10+50.00	M3-2(2412)	2.00		15	
RT STA 10+50.00	M1-1100(2424)	4.00			
RT STA 10+50.00	M6-1L(2115)	2.19			
RT STA 10+50.00	M3-3(2412)	2.00			
RT STA 10+50.00	M1-1100(2424)	4.00			
RT STA 10+50.00	M6-1R(2115)	2.19			
IL 159 (N-S PORTION)					
RT STA 104+25.00	M2-1(2115)	2.19		15	
RT STA 104+25.00	M1-1100(2424)	4.00			
LT STA 105+00.00	R2-1(3036)	7.50		15	
RT STA 106+25.00	SIGN003		21.00	30	
LT STA 106+50.00	SIGN004		17.50	30	
LT STA 107+50.00	M3-3(2412)	2.00		15	
LT STA 107+50.00	M1-1100(2424)	4.00			
RT STA 109+10.00	M3-4(2412)	2.00		15	
RT STA 109+10.00	M1-1100(2424)	4.00			
RT STA 109+10.00	M6-1L(2115)	2.19			
RT STA 109+10.00	M3-2(2412)	2.00			
RT STA 109+10.00	M1-1100(2424)	4.00			
RT STA 109+10.00	M6-3(2115)	2.19			
RT STA 109+10.00	M4-6(2412)	2.00			
RT STA 109+10.00	M1-1100(2424)	4.00			
LT STA 110+50.00	M3-3(2412)	2.00		15	
LT STA 110+50.00	M1-1100(2424)	4.00			
LT STA 110+50.00	M6-3(2115)	2.19			
LT STA 110+50.00	M3-4(2412)	2.00			
LT STA 110+50.00	M1-1100(2424)	4.00			
LT STA 110+50.00	M6-1R(2115)	2.19			
RT STA 112+00.00	M3-2(2412)	2.00		15	
RT STA 112+00.00	M1-1100(2424)	4.00			
RT STA 114+00.00	SIGN005		14.38	30	
LT STA 114+75.00	SIGN006			30	
RT STA 115+50.00	R2-1(3036)	7.50		15	
LT STA 116+75.00	M3-3(2412)	2.00		15	
LT STA 116+75.00	M1-1100(2424)	4.00			
LT STA 116+75.00	M6-3(2115)	2.19			
LT STA 116+75.00	M3-4(2412)	2.00			
LT STA 116+75.00	M1-1100(2424)	4.00			
LT STA 116+75.00	M5-1R(2115)	2.19			
LT STA 119+00.00	M2-1(2115)	2.19		15	
LT STA 119+00.00	M1-1100(2424)	4.00			
		190.47	85.38	28.69	450

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	LENGTH (FOOT)	COLOR	# OF LINES	SPACING	QUANTITY (EACH)
PART A					
CENTERLINE					
IL 16 (E-W PORTION)					
STA 1127+21.20 TO STA 1140+52.80	1,331.60	AMBER	1	80	17
IL 159 (N-S PORTION)					
STA 119+12.12 TO STA 118+12.11	100.01	AMBER	1	80	2
STA 118+12.11 TO STA 111+52.10	660.01	AMBER	2	80	18
STA 111+52.10 TO STA 110+37.10	115.00	AMBER	1	80	2
STA 109+26.80 TO STA 108+11.80	115.00	AMBER	1	80	2
STA 108+11.80 TO STA 101+51.80	660.00	AMBER	2	80	18
STA 101+51.80 TO STA 101+26.77	25.03	AMBER	1	80	1
LEFT TURN LANE					
STA 111+52.10 TO STA 110+37.10	115.00	CRYSTAL	1	40	3
STA 109+26.80 TO STA 108+11.80	115.00	CRYSTAL	1	40	3
RIGHT TURN LANE					
STA 112+52.10 TO STA 110+37.10	215.00	CRYSTAL	1	40	6
PART B					
CENTERLINE					
STA 1149+43.64 AH TO STA 1154+95.82 BK	552.18	AMBER	1	80	7
STA 1154+99.92 AH TO STA 1280+02.26 BK	12,502.34	AMBER	1	80	157
STA 1280+11.77 AH TO STA 1293+48.10 BK	1,336.33	AMBER	1	80	17
STA 1293+53.91 AH TO STA 1304+24.50 BK	1,070.59	AMBER	1	80	14
STA 104+01.66 AH TO STA 188+25.00	8,423.34	AMBER	1	80	106
PART C					
CENTERLINE					
STA 188+25.00 TO STA 199+94.20	1,169.20	AMBER	1	80	15
STA 199+94.20 TO STA 201+26.00	131.80	AMBER	2	80	4
STA 0+00.00 TO STA 0+99.00	99.00	AMBER	2	80	4
STA 0+99.00 TO STA 30+00.00	2,901.00	AMBER	1	80	37
PART D					
CENTERLINE					
STA 30+00.00 TO STA 30+61.01 BK	61.01	AMBER	1	80	1
STA 31+09.65 AH TO STA 51+64.30 BK	2,054.65	AMBER	1	80	26
STA 53+55.92 AH TO STA 91+74.78 BK	3,818.86	AMBER	1	80	48
STA 91+75.20 AH TO STA 106+20.58 BK	1,445.38	AMBER	1	80	19
STA 106+24.40 AH TO STA 124+31.79 BK	1,807.39	AMBER	1	80	23
STA 124+36.47 AH TO STA 165+49.56 BK	4,113.09	AMBER	1	80	52
STA 165+56.00 AH TO STA 175+07.05	951.05	AMBER	1	80	12
					614

PLOT DATE : #DATES
 FILE NAME : #FILE#
 PLOT SCALE : #SCALE#
 USER NAME : #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 325 (IL 16) & FAP 604 (IL 159)
 14R; 115RS-2; 116RS-4; 101RS-2
 MACOUPIN COUNTY
 SCALE: VERT. _____ DRAWN BY _____
 HORIZ. _____ CHECKED BY _____
 DATE _____