

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	4
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS 4007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
X0325368	TRENCHLESS PIPE INSTALLATION 60"	FOOT	1,041	1,041	0	0	0
X0325309	TRENCHLESS PIPE INSTALLATION 54"	FOOT	108	108	0	0	0
Z0038506	REMOVE PERMANENT BARRICADES	L SUM	1	1	0	0	0
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,693	2,693	0	0	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	965	965	0	0	0
20100500	TREE REMOVAL, ACRES	ACRE	53	53	0.0	0.0	0.0
20200100	EARTH EXCAVATION	CU YD	715,002	715,002	0	0	0
20200200	ROCK EXCAVATION	CU YD	17,593	17,593	0	0	0
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	1,100	1,100	0	0	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	600	600	0	0	0
20300100	CHANNEL EXCAVATION	CU YD	1,025	1,025	0	0	0
20400800	FURNISHED EXCAVATION	CU YD	415,524	415,524	0	0	0
20800150	TRENCH BACKFILL	CU YD	5,734	5,734	0	0	0
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	56,238	56,238	0	0	0

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:  
DATE: MARCH 10, 2006

DRAWN BY: RG  
CHECKED BY: JAC

Rev.