

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	9
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS FED. AID PROJECT			

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS 4007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
* 50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1359	1359	0	0	0
50800105	REINFORCEMENT BARS	POUND	184,730	0	184,730	0	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	51,610	51,610	0	0	0
51500100	NAME PLATES	EACH	3	1	2	0	0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	166	0	166	0	0
54003000	CONCRETE BOX CULVERTS	CU YD	939.9	0.0	939.9	0.0	0.0
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	104	104	0	0	0
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	21	21	0	0	0
54200451	PIPE CULVERTS, TYPE 1 RCCP 36"	FOOT	6	6	0	0	0
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	84	84	0	0	0
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	825	825	0	0	0
54200655	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"	FOOT	118	118	0	0	0
54200685	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 60"	FOOT	124	124	0	0	0
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	1,658	1,658	0	0	0

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC