

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	13
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS FED. AID PROJECT			

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS 4007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
54218462	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 36" RISER	EACH	2	2	0	0	0
54218484	REINFORCED CONCRETE PIPE TEE, 60" PIPE WITH 36" RISER	EACH	1	1	0	0	0
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	100	100	0	0	0
5422D024	PIPE CULVERTS, CLASS D, TYPE 2 24" (TEMPORARY)	FOOT	100	100	0	0	0
5422D030	PIPE CULVERTS, CLASS D, TYPE 2 30" (TEMPORARY)	FOOT	219	219	0	0	0
5423D024	PIPE CULVERTS, CLASS D, TYPE 3 24" (TEMPORARY)	FOOT	132	132	0	0	0
5423D030	PIPE CULVERTS, CLASS D, TYPE 3 30" (TEMPORARY)	FOOT	194	194	0	0	0
5423D042	PIPE CULVERTS, CLASS D, TYPE 3 42" (TEMPORARY)	FOOT	108	108	0	0	0
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1	0	0	0
54248510	CONCRETE COLLAR	CU YD	28.7	28.7	0.0	0.0	0.0
5425D030	PIPE CULVERTS, CLASS D, TYPE 5 30" (TEMPORARY)	FOOT	138	138	0	0	0
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	42	42	0	0	0
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	414	414	0	0	0

59100100 GEOCOMPOSITE WALL DRAIN

SQ YD

262

262

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC

Rev.