

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	20
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS FED. AID PROJECT			

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS 1007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	0	0	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,015	1,015	0	0	0
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	0	0	0	1
* 80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	1	0	0	0	1
* 80803100	WOOD LIGHTING POLE, 50 FOOT, CLASS 3	EACH	10	0	0	0	10
* 81800620	AERIAL CABLE, 2-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE	FOOT	1,800	0	0	0	1,800
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	10	0	0	0	10
* 82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1	0	0	0	1
X0301728	CONCRETE COLLAR, SPECIAL	CU YD	129.7	129.7	0	0	0
X0322729	MATERIAL TRANSFER DEVICE	TON	29,797	29,797	0	0	0
X0323092	HEADWALL REMOVAL	EACH	17	17	0	0	0
X0323660	DROP BOX NO. 1	EACH	1	1	0	0	0
X0323661	DROP BOX NO. 2	EACH	1	1	0	0	0
X0323662	DROP BOX NO. 3	EACH	1	1	0	0	0

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:
DATE: MARCH 10, 2006

DRAWN BY: RG
CHECKED BY: JAC