

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	21
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	ROADWAY 1000-2A	CULVERTS Y007	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
X0323665	RIPRAP SLURRY	SQ YD	2	2	0	0	0
X0323718	PUMP POND DRY	L SUM	1	1	0	0	0
* X0324455	DRILLING AND SETTING SOLDIER PILES ( IN SOIL)	CU FT	2540	2540	0.0	0.0	0.0
* X0324456	DRILLING AND SETTING SOLDIER PILES ( IN ROCK)	CU FT	4637	4637	0.0	0.0	0.0
X0545000	BOX CULVERT REMOVAL	FOOT	64	64	0	0	0
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	11,669	11,669	0	0	0
* X2020500	EARTH EXCAVATION (ROCKFILL)	CU YD	1,020	1,020	0	0	0
X2503000	MAINTENANCE MOWING	ACRE	100	100	0	0	0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	665	665	0	0	0
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	949	949	0	0	0
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	1,108	1,108	0	0	0
X4066910	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	475	475	0	0	0
X4073081	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 10"	SQ YD	11,195	11,195	0	0	0
X4073146	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/4"	SQ YD	143,730	143,730	0	0	0

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:  
DATE: MARCH 10, 2006

DRAWN BY: RG  
CHECKED BY: JAC

Rev.