

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	29
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS FED. AID PROJECT		

## SCHEDULE OF QUANTITIES

### R-O-W MARKER REMOVAL SCHEDULE

STATION	OFFSET	LT/RT	XX001017
			REM R-O-W MARKERS (EACH)
1189+71	7	RT	1
1192+71	137	RT	1
1192+71	22	RT	1
1196+71	172	RT	1
1210+71	157	RT	1
1212+21	157	RT	1
1214+71	167	RT	1
1215+44	17	RT	1
1221+71	27	RT	1
1223+71	27	RT	1
1228+19	37	RT	1
1230+28	28	RT	1
1234+34	42	LT	1
1236+60	161	LT	1
1237+26	119	RT	1
1275+34	37	RT	1
1282+18	5	RT	1
1282+17	5	LT	1
1284+81	5	LT	1
1312+92	66	LT	1
1315+54	109	LT	1
32+84	6	LT	1
1316+85	150	LT	1
1317+50	97	LT	1
1317+51	87	LT	1
1317+54	104	LT	1
1348+13	69	LT	1
1348+52	114	RT	1
1353+05	50	LT	1
1359+19	149	RT	1
1362+75	92	RT	1
1369+54	96	RT	1
1370+55	19	LT	1
1372+55	18	LT	1
1382+55	33	LT	1
1384+55	33	LT	1
1387+74	102	RT	1
1387+86	138	RT	1
1388+66	134	RT	1
1388+74	87	RT	1
1401+46	69	LT	1
1401+96	69	LT	1
1402+45	24	LT	1
1403+00	101	RT	1
TOTAL			44
USE			44

### BUILDING REMOVAL SCHEDULE

BUILDING NO.	LOCATION			TYPE	AREA (SQ FT)	BUILDING REMOVAL (L SUM)
	STATION	OFFSET	LT/RT			
1	1182+00	136	LT	SHED	599	1
2	1193+85	142	LT	SHED	152	1
3	1194+21	162	LT	SHED	136	1
4	1194+44	136	LT	SHED	144	1
5	1195+67	141	LT	SHED	195	1
6	1195+80	95	LT	SHED	332	1
7	1202+45	16	RT	HOUSE	1,131	1
8	1209+08	48	LT	MOBILE HOME	573	1
10	1229+62	52	LT	RESIDENCE	1,693	1
13	1232+70	241	RT	STRUCTURE	125	1
14	1236+76	255	LT	SHED	160	1
15	1236+90	328	LT	SHED	1,805	1
16	1237+19	203	LT	GARAGE	967	1
17	1237+69	370	LT	SHED	974	1
18	1238+68	139	LT	GARAGE	1,401	1
19	1238+69	226	LT	GARAGE	502	1
20	1239+10	200	LT	RESIDENCE	1,959	1
21	1239+91	201	LT	SHED	48	1
22	1328+75	152	RT	STEEL STR	684	1
23	1332+70	120	RT	SHED	414	1
TOTAL						20

### WELL AND SEPTIC SCHEDULE

STATION	OFFSET	LOCATION	Z0023900	Z0023800
			FILLING EXISTING WELLS (EACH)	FILLING EXISTING SEPTIC TANK (EACH)
1181+36.00	41	LT	1	1
1195+00.00	62	LT	1	1
1202+40.00	0		1	1
1208+88.00	76	LT	1	1
1229+64.00	3	RT	1	1
1237+75.00	216	LT	1	1
1239+34.00	232	LT	1	1
1255+15.00	140	LT	1	1
1334+80.00	124	LT	1	1
TOTALS			9	9

### PUMP POND DRY SCHEDULE

STATION	LT / RT	X0323718
		PUMP POND DRY (L SUM)
1191+50.00	LT	0.5
1367+00.00	LT	0.5
TOTALS		1
USE		1

### PERMANENT BARRICADE SCHEDULE

STATION	STATION	REMOVE PERMANENT BARRICADES (L SUM)
1165+00	1174+00	1
TOTALS		1

### REMOVAL OF EXISTING STRUCTURES, SPECIAL SCHEDULE

STATION	OFFSET	LOCATION	X5010205
			REMOVAL OF EXISTING STRUCTURES, SPECIAL (EACH)
1209+20.00	100	LT	1
1281+70.00	37	RT	1
1283+50.00	0	RT	1
TOTALS			3

### GUTTER REMOVAL SCHEDULE

STATION	TO	STATION	WB/EB	44000400	44002600
				GUTTER REMOVAL (FOOT)	GUTTER OUTLET REMOVAL (FOOT)
1181+85.00		1182+20.00	WB		35
1182+20.00		1190+03.00	WB	783	
1190+03.00		1190+68.00	WB		65
1181+88.00		1190+56.00	EB	868	
1190+56.00		1191+10.00	EB		54
1215+95.00		1216+57.00	WB		62
1216+05.00		1216+72.00	EB		67
1216+57.00		1221+30.00	WB	473	
1216+72.00		1221+30.00	EB	458	
1221+30.00		1221+42.00	WB		12
1221+30.00		1221+42.00	EB		12
1227+89.00		1228+53.00	WB		64
1228+53.00		1234+51.00	WB	598	
1234+51.00		1235+17.00	WB		66
1236+03.00		1236+15.00	WB		12
1236+15.00		1242+00.00	WB	585	
1292+06.00		1292+98.00	WB		92
1292+98.00		1303+47.00	WB	1,049	
1303+47.00		1304+15.00	WB		68
1312+04.00		1312+16.00	WB		12
1312+16.00		1314+94.00	WB	278	
1314+94.00		1315+56.00	WB		62
1356+25.00		1358+73.00	EB	248	
1356+25.00		1358+92.00	WB	267	
1358+73.00		1358+85.00	EB		12
1358+92.00		1359+04.00	WB		12
TOTAL				5,607	707

\*DDN-SPEC\*  
 \*DATE-TIME\*  
 \*REF 01

06 PROJECT: FILE:

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES OF QUANTITIES

SCALE:  
DATE: MARCH 10, 2006

DRAWN BY: RG  
CHECKED BY: JAC