

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	35
STA.		TO STA.		
FED. ROAD DIST. No.		ILLINOIS FED. AID PROJECT		

## DRAINAGE STRUCTURE SCHEDULE

LOCATION		54217680	54218451	54218462	54218484	54248510	X0301728	MANHOLES					54244405	60246605	60246805	60801042	60405730	X0323660	X0323661	X0323662	
		RCP TEE, 24" PIPE W/ 24" RISER	RCP TEE, 42" PIPE W/ 36" RISER	RCP TEE, 48" PIPE W/ 36" RISER	RCP TEE, 60" PIPE W/ 36" RISER	CONCRETE COLLAR	CONCRETE COLLAR SPECIAL	TY A, 5' DIA, TY 1 FRAME, CL	TY A, 5' DIA, TY 9 FR & GR	TY A, 5' DIA, W/ MEDIAN INLET (604101)	TY A, 6' DIA, TY 1 FRAME, CL	TY A, 6' DIA, W/ MEDIAN INLET (604101)	FLUSH INLET BOX FOR MEDIAN (542546)	MEDIAN INLET (604101)	MEDIAN INLET (604106)	FLAP GATE, 42"	FRAMES AND GRATES	DROP BOX NO. 1	DROP BOX NO. 2	DROP BOX NO. 3	
STATION	LT/RT/AR	(EACH)	(EACH)	(EACH)	(EACH)	(CU YD)	(CU YD)	(EACH)					(EACH)	(EACH)	(EACH)	(EACH)	(POUND)	(EACH)	(EACH)	(EACH)	
1177+00.00	AR										1										
1190+80.00	AR												1								
1192+30.00	AR										1										
1196+45.00	AR			1							1				1						
1201+00.00	RT										1										
1205+04.00	RT										1										
1209+45.00	AR										1										
1215+00.00	LT								1		1										
1222+82.00	AR								1		1										
1236+50.00	LT										1										
1246+88.80	AR																				
1247+00.19	AR						35.6														
1247+11.58	AR																				
1251+25.00	RT								1		1										
1253+54.07	AR																				
1253+60.00							23.8														
1253+65.93	AR																				
1278+11.70						2.8															
1281+00.00	AR		1								1				1						
1286+00.00	RT								1		1										
1289+13.56	RT															1					
1290+31.39	MEDIAN																				
1292+00.00	RT								1												
1294+50.00	MEDIAN																				
1298+68.00	AR								1		1						520	1			
1299+06.80						3.5															
1301+62.05						2.8															
1301+70.00	AR								1		1										
1304+25.90						2.8															
1304+26.11	AR								1		1						520		1		
1308+20.42						2.8															
1308+21.04	AR								1		1										
1323+00.00	RT								1		1										
1328+00.00	RT																				
1334+50.00	AR			1											1		1080				1
1334+78.28						2.8															
1341+40.00	LT																				
1341+55.00	AR											1		1							
1349+83.00	AR						10.9				1										
1352+50.00	LT								1		1										
1336+48.65						2.8															
1367+00.00	LT	1							1				1	1							

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES OF QUANTITIES

SCALE: DATE: MARCH 10, 2006  
 DRAWN BY: RG  
 CHECKED BY: JAC

\*DGN: SPEC\*  
 \*DATE: TIME\*  
 \*REF: 01